



MAP OF THE TOWN OF
BURKEMONT.

Union County, Oregon.
One quarter mile south of the
Great Copper Property owned
by the North American Mining Company.

Fraudlyn Avenue 80 feet wide. All other Streets
and Avenues are 60 feet wide. Alleys 16 feet wide.
Blocks 200 x 300 feet = Lots 25 x 92 feet in Blocks
6-7-8-9-10-11-12-13-14-15. Lots 50 x 92 feet in Blocks
1-2-3-4-5-16-17-18-19. Blocks and Alley stakes
are 2 x 2 inches. Lot stakes are 1 x 2 inches.

Survey Notes.

Beginning at a cut stone 8 x 8 inches set 18 inches in
ground at a point on section line 696 feet S. 89° 56' N.
from the original corner to sections 27-28-33-34 2p. 7. S.R.
42 E. N. M.
Running thence north 537.90 feet to corner no. 1 a stone
set in ground. Thence N. 42° 37' N. 185.63 feet to corner no. 2
set in ground. Thence west 134.32 feet to corner no. 3 stone
set in ground. Thence north 223.40 feet to corner no. 4. Stone
set in ground. Thence N. 42° 37' N. 185.63 feet to corner
no. 5 stone set in ground. Thence West 734.32 feet to corner
no. 6 stone set in ground. Thence South 975.76 feet to a cut
stone 8 x 8 inches and 18 inches in ground at a point on line
between sections 28 & 33. 1860 feet to corner no. 7. Stone set
in ground. Thence east 880 feet to corner no. 8 stone set
in ground. Thence N. 53° 7' E. 300.05 feet to corner no. 9 stone
set in ground. Thence north 705.41 feet to place of beginning.
Being a part of the S.E. 1/4 S.E. 1/4 & part of the S.W. 1/4 S.E. 1/4 of
Section 28 and a part of the N.E. 1/4 N.E. 1/4 and part of the N.W. 1/4
N.E. 1/4 of section 33 2p. 7. S.R. 42. E. N. M. containing 44.78 acres.

Mg. Va. 20° 15' E.
Scale 125 feet to one inch.

Recorded July 16th 1900. at 3 P.M.
John M. Sillescu
Recorder
Union Co. Ore.

For Original see
Deed Record
Volume 57, Page 233

Not Legal, for Correct Plat, See Page, 19. this Book.