

76 Surveyed for James Moss Dec 28 1888

By W. Kimbrell County Surveyor Plat No. 66

I commenced at the corner to
 Sec 16=17=20 of 21 thence South
 2000 let stake for temporary 1/8 corner
 7000 chas let stake for temporary
 1/4 sec one 8016 chains the S.E. corner
 Sec 20 from which I run North 4008
 chains let stone marked for 1/4 sec one
 between Sec 20 & 21 6012 chains let stake
 for 1/8 corner on East side N.E. 1/4 Sec 20
 8016 chas N.E. corner Sec 20 thence
 West 40 chains let stake for temporary
 1/4 sec one 6030 chains 1/8 corner from
 which I run East 2010 chains let
 stone marked for 1/4 sec one between

		James Moss
	Sec 20	

Sec 17 & 20 I then started at the S.E. corner Sec 20
 thence West 402 1/2 chains let stake for temporary 1/4 sec corner
 8005 chains let stake for temporary 1/4 sec one thence West
 4000 chains let stake for temporary 1/4 sec one 7902 chains
 the S.W. corner Sec 19 making an excess of 114 links
 over the original U.S. field notes I therefore run East
 3816 chains let stone marked for 1/4 sec corner between
 Sec. 19 & 20 and at 7845 chains let stake for one
 to Sec 19=20=29 & 30 thence East 4030 chains let
 stake for 1/4 sec one between Sec 20 & 29 8062 chas
 the corner to Sec 28=29=20 & 21

I then started at the N.W. corner Sec 20 thence South
 40 chains let stake for temporary 1/4 sec one 80 chas
 let stake for temporary 1/4 sec one thence South 40 chas
 let stake for temporary 1/4 sec one 80 chas find no one at
 4106 chas the 1/4 sec one between Sec 30 & 32 making an
 excess of 106 chains over U.S. field notes I therefore run
 North allowing 2 links to each 1/2 mile to the corner
 to Sec 19=20=29 & 30 and set post in place but
 suspend establishing the corner proper as per instructions
 by proportional measurement, as the point of intersection
 at post in place is disputed by the settlers and
 think they can establish the fact that the original
 corner established by U.S. setts was about 150

See Page 76 Plat 66 James Moss 77

West of Post but I have previously run and
 chained East from this point 5 miles to East
 boundary of Township and find the excess
 to be within 1 link of the same excess
 I then started at 1/4 sec Point on South Side
 Sec 20 thence North through center Sec 20
 at 30 chains let stake for temporary fractional
 corner at 40 chains let stake for temporary center
 60 chais let stake for temporary 1/8 one 8032 chais
 the 1/4 sec one on North side Sec 20 from
 which I run South 2008 chains let stone
 for 1/8 corner James Moss S.W. one 4016 chais
 center Sec 20 at 5026 chais let stake for
 fractional corner to side of Oliver
 the 1/4 sec corner on West side Sec 20 thence
 East through center Sec 20 at 8078
 chains the 1/4 sec one on East side Sec
 20
 W. Kimbrell County Surveyor