

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. L-3

History of original corner establishment:

Corner was set October 1, 1979 under U.S.F.S. Contract

Hanley Engineering had information that placed the section corner for sections 7, 8, 17 and 18 to a new position. I agreed to this position and they monumented the corner in March, 1981. The new position moved this corner and it was reset April 8, 1981.

DIAGRAM

T6SR38E

C 1/4 — S18

Description of corner evidence found:

Corner falls about 300' north of track road in scattered timber.

Description of monument and accessories I established to perpetuate the original location of this corner:

At new surveyed point set 2 1/2" X 30" galvanized pipe and brass cap set in 1979. Cap Marked:
Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination N20°E:

A 16" Tamarac bears S62 1/2°E, 74.6 ft. scribed C 1/4 S18 BT.

A 12" Tamarac bears N16°W, 30.7 ft. scribed C 1/4 S18 BT.

These are the 1979 BTs.

Placed 54-3s and 54-9s and brass washers marked PLS 1051 on BTs.

Placed 54-9 on steel fence post 5' west of the corner.

RESET 1981
T6SR38E

C 1/4 — S18

OR PLS 1051
1979

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Douglas Moser

April 8, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the.....day of.....June....., 19⁸¹
.....by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED June 23, 1981

CLATSOP COUNTY SURVEYOR

FILE NO. 6-38-4

amended- originally filed Dec. 6, 1979