


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. N-3

History of original corner establishment:

Corner was originally established by W. B. Barr, under GLO contract No. 388, in September, 1881. Surveyors General's notes state: "Set stake 4 ft. long, 4 ins. diam. 18 ins. in ground for 1/4 Sec. corner from which a Pine 5 ins. diam. brs. N79°W, 35 lks. dist. a Fir 6 ins. diam. brs. S47°E, 5 lks. dist."



Description of corner evidence found:

Found no trace of original corner during two searches.
Corner falls about 25' West of old logging road.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked:
Set pipe 24" in the ground and small mound of stone around to cap.
From which, by magnetic declination of N20°E:
A 10" tamarac bears N10°E, 34.5 ft. scribed 1/4 S18 BT. A 10" pine bears S60°W, 46.7 ft. scribed 1/4 S19 BT. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Painted blazes red and 6" red band around. Placed 54-4 on steel fence post 5' West of corner.

T6SR38E
S18


1/4 ———+————

S19
OR PLS 1051
1979


I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Jerry Rous
Doris Grey

October 1, 1979



Barry B. Barbour



Office of.....County Surveyor..... County of.....~~Huachuca~~ Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...6th day of...December....., 1979.
.....by *Thomas J. Hanley*.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Dec 6, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 6-38-6

☆ GPO—758-276