

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. N-5

History of original corner establishment:

Corner was originally established by W. B. Barr, under G.L.O. contract No. 388, in September, 1881. Surveyors General's notes state: "Marked slate stone 26 x 8 x 8 for corner to Secs. 17, 18, 19, and 20 From which A pine 8 ins. diam. brs. S19°E, 41 lks. dist. A pine 14 ins. diam. brs. S10°W, 57 lks. dist. A pine 26 ins. diam. brs. N43 1/2 °W, 57 lks. dist. A pine 36 ins. diam. brs. N45°E, 69 lks. dist."

DIAGRAM

```

T6SR38E
S18 | S17
  + 
S19 | S20
    
```

Description of corner evidence found:

Found 27 x 8 x 7 inch slate stone with 3 notches on south and 5 notches on east edges. A pine stump scribed "BT" bears S15°W, 37 ft. Stump N42°W, 35.0 ft., no scribing. A stump bears N48°E 45.3 ft., no scribing. Note. Near an East-West fence and compass may be pulled. SW stump has 54-3.

Description of monument and accessories | established to perpetuate the original location of this corner:

At center of above described stone set 2 1/2" x 30" galvanized pipe and brass cap marked: Set pipe 22" in the ground and mound of stone around to cap. Placed marked stone at base of pipe.

```

T6SR38E
S18 | S17
  + 
S19 | S20
OR PLS 1051
1979
    
```

From which, by magnetic declination of N20°E:
 A 12" pine bears N36°E, 25.4 ft. scribed T6SR38E S17 BT.
 A 10" pine bears S42°E, 39.3 ft. scribed T6SR38E S20 BT. A 12" fir bears S56°W, 51.8 ft. scribed T6SR38E S19 BT. A 12" fir bears N45°W, 33.6 ft. scribed T6SR38E S18 BT. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Painted blazes red and 6" red band around. Placed 54-5 on tree 5' East. Placed 54-4 on steel fence post 5' North of corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
 Robert S. Stevens

July 20, 1979

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of... County Surveyor... County of... Baker
 State of... Oregon... I hereby certify that the within instrument was filed in this office
 for record on the... 6th day of... December... 19... 79
 by *Thomas J. Hamby*
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Dec 6, 1979
 BAKER COUNTY SURVEYOR
 SURVEY NO. 6-38-7

☆ GPO—798-278