

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Indes File No. P-1

History of original corner establishment:

Corner was originally established by W. B. Barr, under G. L. O. contract No. 388, in September, 1881. Surveyors General's notes state; "Marked fir 18 in. diam. for 1/4 sec. corner from which a Fir 14 in. diam. bears N5°W, 5 lks. dist., a Fir 14 in. diam. bears S73°E, 38 lks. dist."

DIAGRAM

T6SR38E
S19
R37E — W1/4

Description of corner evidence found:

Found 24" white fir snag scribed "1/4 S" on west face. A 16" white fir snag scribed "1/4 S BT" bears N5°W, 3.2 ft.

Description of monument and accessories established to perpetuate the original location of this corner:

Unable to set pipe at snag, measured North 6.0 ft. from center of snag and set Witness Corner for 1/4 section corner. Set 2 1/2" X 30" galvanized pipe and brass cap marked:
Set pipe 25" in the ground and mound of stone around to cap.

W.C. 6FT NO.
T6SR38E
S19
R37E — W1/4
OR PLS 1051
1979

From which: by magnetic declination of N20°E;
A 15" tamarac bears N76°E, 37.5 ft. scribed W. C.
1/4S19 BT. A 9" tamarac bears S22°W, 17.7 ft. scribed W. C.
T6SR37E BT. Painted blazes red and 6" red band around. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-5 on old BT. Placed 54-2 and 54-4 on steel fence post 5' North of corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Robert S. Stevens

July 20, 1979

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..6th day of..December....., 1979
.....by.....*Thomas J. Henry*.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Dec. 6, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 6-38-8

☆ GPO—798-278