


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. T-1

History of original corner establishment:

Corner was originally established by W. B. Barr, under G.L.O. contract No. 388, in September, 1881. Surveyors General's notes state: "Set stake 4 ft. long 4 in. diam. 18 in. in ground for 1/4 sec. corner from which Pine 48 in. diam. bears West, 20 lks. dist. Pine 30 in. diam. bears S65°E, 47 lks. dist."

DIAGRAM




Description of corner evidence found:

Found one large rotten pine stump near two others. Measured record and found charcoal and 4" x 3" x 2" charred wood about 18" below the ground. Area of East BT has been bladed.

Description of monument and accessories | established to perpetuate the original location of this corner:

Unable to set corner. At single proportionate distance set 2 1/2" x 30" galvanized pipe and brass cap marked:
Set pipe 25" in the ground. No rock in the area.
From which, by magnetic declination of N20°E:
A 14" tamarac bears S50°E, 104.5 ft. scribed 1/4 S30 BT. An 11" tamarac bears N36°W, 55.4 ft. scribed T6SR37E BT. Placed 54-3s and brass washers stamped PLS 1051 on BTs. Placed 54-5 on tree 10' SW of corner. Painted blazes red and 6" red band around. Placed 54-2 and 54-4 on steel fence post 5' South of corner.



I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David L. Landers
Robert S. Stevens

July 26, 1979

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County.....Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 6th day of.....December....., 1979
..... by *Thomas J. Hendley*.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Dec. 6, 1979
BAKER COUNTY SURVEYOR
SURVEY NO. 6-38-10

☆ GPO—755:276