

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established in 1863, by Timothy M. Davenport, under "General Land Office Contract" No. 102.

DIAGRAM
BLM
T6S R38E
S321833

S 518 4
1974

In 1974 the Bureau of Land Management Remonumented this corner. From existing physical evidence. See FIELD NOTES of the "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINT, TOWNSHIP 7 SOUTH, RANGE 38 EAST," as executed by Lester E. Fischer, Cadastral Surveyor and James J. Carlson, Cadastral Surveyor, under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey Group No. 350.

Description of corner evidence found:

Found 2-1/2' iron pipe with 3" brass cap stamped as shown on the, DIAGRAM.
Found remains of original bearing trees.
A decayed ponderosa pine stump, 24 ins. diam., bears N.65E., 389 lks. dist., no marks visible. this stump is decayed beyond repair.
A ponderosa pine stump, 36 ins. diam., bears S.22E., 236 lks. dist., with scribe marks S4 T7S R38E visible on open blaze.
A ponderosa pine stump, 40 ins. diam., bears S.55W., 508 lks. dist., no marks.
Found trees as taken by the BLM in 1974,
A ponderosa pine, 10 ins. diam., live in good condition, bears N.50E., 89 lks. dist., mkd. T6S R38E S33 BT
A ponderosa pine, 13 ins. diam., live in good condition, bears S.50E., 147 lks. dist., mkd. T7S R38E S4 BT
A ponderosa pine, 12 ins. diam., cut off above blaze, bears S.55W., 148 lks. dist., mkd. T7S R38E S5 BT
A fir, 6 ins. diam., live in good condition, bears N.42W., 139 lks. dist., mkd. T6S R38E S32 BT
Accessories established to perpetuate the original location of this corner:

Maintained Corner monument by setting a steel post with warning sign. North 1 ft. from cor.

Maintained remains of original bearing trees by painting a 6" red band around, and nailing a Bearing tree sign above blaze & warning sign to the back of each tree.

Maintained Bearing trees as taken by the BLM in 1974 as follows.
S33 BT, Painted a 6" red band around tree and nailed a warning sign to the back of the tree. Bearing tree sign by John Mitchell is O.K.
S4 and S32 Bearing trees are maintained in the same manner as the S33 BT.
S5 BT, also maintained by painting a 6" red band around tree and nailing warning sign to back of the tree, in addition a bearing tree sign is nailed above the blaze.

Scribed a new bearing tree.
A pine 13" dia. bears S86W., 82.0 ft. scribed, T7S R38E S5 BT
Nailed a brass washer stamped PLS 848, on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of the new tree.
Painted a 6" red band at breast ht. around new tree.
(Douglas M. Ferguson, PLS 848 scribed tree)

Corner Maintained Sept. 19, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

★ 600-700-270

FILED 2-15-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-38-33
6-38-17