

History of original corner establishment:

Corner originally established in 1881, by W. B. Barr, under "General Land Office Contract" No. 388, Surveyor Generals Notes States:
 Set stake 4 ft. long 4 in. diam. 18 in. in ground for 1/4 sec corner, from which
 Tamarack 18 in. diam. bears S60W 8 lks dist.
 " 20 " " " N65W 18 " "

DIAGRAM

T6S R38E
 S32
 1/4-.-
 S 5
 T7S
 1984
 PLB 2065

James D. Hanley, Baker County Surveyor, stated that he found a 1" iron pin, in 1949 and over a period of time whereby he found other similar pins in the area which fit surrounding evidence, he came to accept this pin as a perpetuation of the original corner. In 1981 William L. Hanley, PLB 1639 found this same pin, and after finding that it fits surrounding evidence, he also accepted this pin as the 1/4 cor. position, and used it in the subdivision of Section 5. (see Baker County Survey No. 7-38-20)

Description of corner evidence found:

Found a 1" iron pin, set approx. 20 ft. west from edge of Anthony Lakes Highway.
 No evidence of original stake found, road work and fencing in the area have destroyed all traces.

The original bearing trees have been lost to road work and fencing in the area.

Because of a logical acceptance of the 1" iron pin by previous surveyors it is accepted as the best available evidence of a perpetuation of the original corner position. (See map of Survey)

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2-1/2" aluminum pipe with 2-1/2" aluminum cap stamped as shown on the DIAGRAM, set 28" in the ground. Set the 1" iron pin alongside pipe.

From Which:

A Pine 18" dia. bears N57E., 26.3 ft. scribed 1/4 S32 BT.
 A Pine 12" dia. bears S36W., 18.7 ft. scribed 1/4 S5 BT.

Nailed a brass washer stamped PLB 848, on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree.
 (Douglas M. Ferguson, PLB 848 scribed trees)

Set steel posts with warning and boundary signs, South & West 4 ft. from corner.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

J David Brinton

OREGON
 DECEMBER 2, 1983
 J. DAVID BRINTON
 2065

Corner set Sept. 20, 1984
 Witnessed by Douglas M. Ferguson, PLB 848

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)