

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established in 1881, by W. B. Barr, under "General Land Office Contract" No. 388, Surveyor General's Notes States (Abridged Notes) Set stake for cor. 5,6,31,32 from which Fir 26in diam bears S51E 83 lks dist.
 Pine 14" " " S73W 41 " "
 " 26" " " N20W 23 " "
 " 30" " " N31E 43 " "

DIAGRAM
 B.L.M.
 T6S R38E
 S31E S32

 S61S5
 T7S
 1974

In 1974 the Bureau of Land Management Remonumented this corner. from existing physical evidence. See FIELD NOTES of the "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINT, TOWNSHIP 7 SOUTH, RANGE 38 EAST," as executed by Lester E. Fischer, Cadastral Surveyor and James J. Carlson, Cadastral Surveyor, under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey Group No. 350.

Description of corner evidence found:

Found 2 1/2" iron pipe with 3" brass cap stamped as shown on the DIAGRAM set with 4" above the ground.

Found original bearing trees:

A Ponderosa pine stump, 24 ins. diam., bears S.73W., 41 lks. dist., with fragmentary scribe marks visible on open blaze.
 A decayed ponderosa pine stump, size indeterminate, bears N. 20W., 23 lks. dist., with scribe mark S visible on pitch slab.

Found trees as taken by the BLM in 1974:

A western larch, (tamarack) 9 ins. diam., standing and dead, bears N.40E., 56 lks. dist., mkd. T6S R38E S32 BT.
 A fir, 10 ins. diam., live in good condition bears S.68E., 5 lks. dist. mkd. T7S R38E S5 BT.
 A fir, 10 ins. diam., live in good condition bears S.18W., 12 lks. dist. mkd. T7S R38E S6 BT
 A western larch (tamarack) 9 ins. diam., live in good condition, bears N.14W., 49 lks. dist. mkd. T6S R38E S31 BT.

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained Corner Monument by setting steel fence posts with warning and boundary signs South & East 5 ft. from Cor.

Maintained accessories as follows:

Nailed bearing tree and warning signs to original (stump) bearing trees and painted 6" red band around each stump.

Nailed warning signs to back of trees as taken by the BLM in 1974 and painted a 6" red band around those trees as breast ht. Bearing tree signs as placed by John Mitchell in 1976 are all in good condition.

Scribed a new bearing tree:

A Tamarack 6" dia. bears N77E., 11.7 ft. scribed. X BT
 Nailed a brass washer stamped PLS 848, on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of the new tree. Painted a 6" red band at breast ht. around the new tree.
 (Douglas M. Ferguson, PLS 848 scribed new tree)

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

J. David Brinton

OREGON
 DECEMBER 2, 1983
 J. DAVID BRINTON
 2065

Corner Maintained Sept. 22, 1984
 Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)