

History of original corner establishment:

Corner originally established in 1881, by W. B. Barr, under "General Land Office Contract" No. 388, Surveyor General's Notes States: Set stake 4 ft. long 4 in. diam., 18 in. in ground for 1/4 sec. corner. from which
Fir 14 in dia bears N57W, 11 lks. dist.
Fir 12 " " " S86E, 7 lks. dist.
(at 2.10 ch. west, Creek 4 lks wide flows N45E)

DIAGRAM

T65 R38E
S31
1/4--
S 6
T78
1984
PLS 2065

Description of corner evidence found:

No evidence of original stake found, corner fall in dozed out trail where fence is constructed.

No evidence of original bearing trees found, as they have also been destroyed by the fence trail.

Position set by Proportionate measurement conforms to call to the Creek 2.10 Ch. west. Therefore accepted the proportion position as the 1/4 Cor.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2" aluminum pipe with 2-1/2" aluminum cap stamped as shown on the DIAGRAM, set 14" in the ground and raised a mound of stone and earth around the pipe. Corner is at the base of an earth cut slope in fencing trail.

From which

A white fir 40" dia. bears S83W., 52.3 ft. scribed 1/4 S6 BT, (No smaller trees are available, this tree is not a good saw log, but will make a good accessory even if cut.)

A spruce 7" dia. bears N52E., 42.7 ft. scribed 1/4 S31 BT

Nailed a brass washer stamped PLS 848, on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree.

(Douglas M. Ferguson, PLS 848 scribed trees)

Set a steel post with warning sign North 5 ft. from corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

Corner set Sept. 21, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)