

NARRATIVE TO ACCOMPANY BAKER COUNTY SURVEYS

NOS. 6-39-1 and 6-39-2

This part of narrative describes corner monumentation found and/or established during the course of Farmers Home Administration Survey in Sections 23, 24, 25 and 26, T. 6 S., R. 39 E., W.M. under the above filing numbers.

The original monumentation was established by use of wood posts, set in mounds of earth. This survey has accepted the fence corners at these locations as having perpetuated the locations as originally established. Except as indicated otherwise, the only existing remains of these posts were found at the corner common to Sections 23, 24, 25 and 26, and at the quarter corner between Sections 23 and 24. Marked stones were found along the East line of the township (Guide Meridian) for the Southeast and Northeast corners of Section 25 and the quarter corner between Sections 23 and 24, and were accepted as replacements for the original wood posts, although no documentation was found for the monumentation.

T. Davenport surveyed the East Range line of T. 6 S., R. 39 E. under GLO Contract No. 102, approved 1/12/1864.

D. Thompson surveyed the interior of this township under GLO Contract No. 103, approved 1/20/1864.

N-17 Corner common to Sections 14, 15, 22 and 23: GLO records state "set post for corner to Sections 14, 15, 22 and 23". Found a 3/4-inch diam. pipe in 3-way fence intersection. Point not remonumented.

N-19 Quarter corner between Sections 14 and 23: GLO records state "set post for corner in mound of earth". Found a 3-way fence intersection. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206 at cor point.

N-21 Corner common to Sections 13, 14, 23 and 24: GLO records state: "set post for corner to Secs. 13, 14, 23 and 24 in mound of earth". Found 2-way fence corner. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206 at corner point.

N-23 Quarter corner between Sections 13 and 24: GLO records state "set post for corner...in mound of earth". Found 4-way fence corner. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206.

P-17 Quarter corner between Sections 22 and 23: GLO record states "set post for corner ...in mound of earth"... Extended the North and East running fence lines South and West to intersection point. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206.

P-21 Quarter corner between Sections 23 and 24: GLO record states "set post for corner in mound of earth...". Found remains of rotted post in center of 5 stone mound located in North-South running fence line. Set 2½-inch brass cap on 1¼-inch iron pipe projecting 4 inches above ground with 24-inch stone mound around monument. Set fence post