

T 6 S R 39 E

one foot West of monument.

Monument mkd. thus: 
$$\begin{array}{c|c} S 23 & S 24 \\ \hline CS 1989 & \end{array}$$

R-17 Corner common to Sections 22, 23, 26 and 27: GLO records state "set post for corner to Sections 22, 23, 26 and 27 in mound of earth...". Found 4-way fence intersection. Point not monumented this survey.

R-19 Quarter corner common to Sections 23 and 26: GLO records state "set post for corner in mound of earth". Found fence corner, fence runs North, West and Southeasterly. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206.

R-21 Corner common to Sections 23, 24, 25 and 26: GLO records state "set post for corner to Sections 23, 24, 25 and 26 in mound of earth with charred stake..". Found charcoal remains one foot under surface in center of 3 stone mound (large stones) in ancient fenceline remains. Set 2½-inch brass cap on 1¼-inch diam. iron pipe projecting 2 inches above ground with 36 inch diam. stone mound around the monument. Set fence post alongside.

T 6 S R 39 E

Monument mkd. thus: 
$$\begin{array}{c|c} S 23 & S 24 \\ \hline S 26 & S 25 \\ \hline CS 1989 & \end{array}$$

R-23 Quarter corner between Sections 24 and 25: GLO records state: "set post for corner in mound of earth...". Set a 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGR PLS 1206 in North-South running fence line on line between Southeast and Southwest section corners.

R-25 Corner common to Sections 19, 24, 25 and 30: GLO records state "set post corner to Sections 19, 30, 24 and 25, made mound of earth"... Found a 15 x 11 x 9 inches stone in rock jack mkd. with 6 grooves on each of two sides and 2 grooves on one other side. Accepted rock jack for corner position. Did not remonument.

T-17 Quarter corner between Sections 26 and 27: GLO records state "set post for corner in mound of earth...". Set 2½-inch brass cap on 1¼-inch iron pipe, 30 inches long in 36 inch diam. mound, in North-South running fence line at proportionate distance between Northwest and Southwest section corners.

T 6 S R 39 E

Monument mkd. thus: 
$$\begin{array}{c|c} S 27 & S 26 \\ \hline CS 1989 & \end{array}$$