


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner was originally established by W. B. Barr under Contract No. 388 in August, 1881. The original notes state that a marked basalt rock was set for the corner from which:  
 A 3" Pine bears N 60° E 27 LK.  
 A 4" Pine bears N 28° W 47 LK.




No record of subsequent re-monumentation found in County Records.

Description of corner evidence found:

None.

After a thorough search for corner evidence I set the corner by single proportion measurement along the township line from the found Southeast corner of Section 36 to the found Southwest corner of Section 34.

Description of monument and accessories I established to perpetuate the original location of this corner. At the calculated corner position I set a 2" x 30" iron pipe with 2 1/2" brass cap 18" in the ground with a mound of stone to cap marked:



From which:

A 16" White Fir bears S 27 1/2° W for 22.0 feet, scribed T6S R43E S35 BT.  
 A 16 1/2" Red Fir bears N 72° E for 25.6 feet, scribed T6S R43E S36 BT.  
 An 18" Red Fir bears S 54 1/2° E for 34.8 feet, scribed T7S R43E S1 BT.  
 A 25" Red Fir bears S 64° W for 19.2 feet, scribed T7S R43E S2 BT.  
 All BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush. Attached signs 54-3 and painted red ring around BT's.  
 Set steel fence post with sign 54-9 attached by the monument.

Note: A 13" sick Red Fir bears N 28° E for 1.0 feet (painted red ring around tree).  
 A 20" sick White Fir bears S 13° E for 15.8 feet (started lower blaze then noted tree was sick - no scribing).

Witness: Les Wilson

Used magnetic compass with 20 1/2° E declination and measured to center of root crown on BT's with steel tape.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*William R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

11-1-78

Office of..... County of.....  
 State of..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

\* GPO - 798-276

FILED Nov. 3, 1978

BAKER COUNTY SURVEYOR  
 SURVEY NO. 6-43-19