

DEPENDENT RESURVEY AND PARTIAL SECTION SUBDIVISION

SECTIONS 29, 33, AND 34, T.6S., R.43E., WILLAMETTE MERIDIAN  
 SECTIONS 3, 4, 9 AND 10, T.7S., R.43E., WILLAMETTE MERIDIAN

NATURE AND PURPOSE OF SURVEY

This U. S. Forest Service administrative survey was made for the purpose of establishing the ground position of the legal boundary between National Forest Lands and those described in the current Land Status Records.

The survey required the partial subdivision of Sections 33 and 34, Township 6 South, Range 43 East, Willamette Meridian, and Sections 3 and 4, Township 7 South, Range 43 East, Willamette Meridian, and the establishment of those minor subdivision corners which control the location of the adjoining lands.

HISTORY OF PREVIOUS SURVEYS

The original survey of T.7S., R.43E. was executed by W. B. Barr in 1881, and was approved on December 31, 1881.

The original survey of T.6S., R.43E. was executed by W. B. Barr in 1884, and was approved on March 21, 1885.

The North line of Sections 33 and 34, and the East and South line of Section 34, T.6S., R.43E. were resurveyed by William R. Wells P.L.S. No. 1106 in 1977 and 1978.

In T.7S., R.43E. original corners established by W. B. Barr in 1881 were remonumented by the Bureau of Land Management in 1974.

In T.6S., R.43E. original corners established by W. B. Barr in 1884 were remonumented by the Bureau of Land Management in 1975.

In T.7S., R.43E. original corners established by W. B. Barr in 1881 were remonumented by the Baker County Surveyor in 1980.

In T.6S., R.43E. original corners established by W. B. Barr in 1884 were remonumented by the Baker County Surveyor in 1965.

BASIS OF BEARING

Bearings are oriented to a solar observation taken along the control survey line.

METHOD OF SURVEY

This survey was made with a Wild T-1 Theodolite and Model 112 AGA Geodimeter EDM and with a Model 3810A Hewlett-Packard EDM. All angles were determined by the method of direct angles to the right, and distances measured with EDM's. All traverses were closed to the point of beginning or to a control point on a previously closed traverse.

NOTES

Corner perpetuation and Filing Forms have been filed with the Baker County Recorder in Baker, Oregon.  
 See accompanying sheet for "Narrative of Survey."

LEGEND

- Aluminum capped monument set this survey from survey data.
- Aluminum capped monument set this survey from original evidence.
- Found Brass Cap set by William R. Wells R.L.S. 1106
- Found Brass Cap set by the County Surveyor R.L.S. 1208
- Found Brass Cap set by the U.S. Bureau of Land Management
- ⊙ Corner Tree established during the original survey in 1884.
- Section Lines
- 1/4 Section Lines
- 1/16 Section Lines
- 1/64 Section Lines
- National Forest Boundary posted to standard specifications.
- ( ) Record Data: General Land Office
- [ ] Data From previous surveys
- Ⓣ Corner Monumentation Reference No., See Sheet 4/4

Filed May 9, 1986  
 Baker County Surveyor  
 Survey No. 6-43-81  
 7-43-94

SURVEYORS CERTIFICATE

I, Clyde Porter, a registered professional land surveyor in the State of Oregon, No. 1928, and Duane Fehring, a registered professional land surveyor in the State of Oregon, No. 2118, hereby certify that this plat and notes hereon, or attached, are a correct representation of a survey performed by Duane Fehring, and under our direct supervision during June, July, and August 1984 and June and July 1985 at the request of the U. S. Department of Agriculture, Forest Service, in accordance with the statutes of the State of Oregon and the articles of the contract.

DUANE FEHRINGER  
 1-20-86  
 OREGON  
 JULY 13, 1984  
 DUANE FEHRINGER  
 2118

U. S. DEPARTMENT OF AGRICULTURE FOREST SERVICE	
REGION 6 WALLOWA-WHITMAN NATIONAL FOREST	
GOOSE CADASTRAL SURVEY	
CONTRACT No. 53-04M3-4-2981	
T.6S. & T.7S., R.43E., WILLAMETTE MERIDIAN	
SURVEYED BY: D. F. & D. F.	DATE: 6, 7, 8, 14, & 16, 21, 27, 28
DRAWN BY: D. F.	DATE: 2/85
PORTER'S LAND SURVEYING	BOISE, IDAHO
ENGINEERING SERVICES, INC.	CASPER, WYO.

