

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Original survey executed by W. B. Barr in July 1884 under Contract NO. 503, dated May 23, 1884.

Set granite rock 12"x10"x8" 8" in ground marked "1/4" on north side.

From which: 6" pine bears S.25°W. 23 lks

6" fir bears N.30°W. 19 lks

Both scribed "1/4 S BT"



Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

Set 30" long aluminum pipe with 3 1/4" aluminum cap marked as shown above, 5" above ground. Steel post with sign 54-9 set next to cap.

Scribed:

6" fir N.18°W. 41.5' "1/4 S20 BT"

7" fir S.78°W. 64.5' "1/4 S29 BT"

Attached signs 54-3 & 54-9 and nailed aluminum washers stamped "RLS 1928" by "BT" scribe on each tree. Painted blazes red and a 6" red band around both trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
1-20-86
Duane Fehringer
OREGON
JULY 13, 1984
DUANE FEHRINGER
2118

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

FILED *May 9, 1986*
BAKER COUNTY SURVEYOR
SURVEY NO. *6-413-89*