

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Original corner established in 1884 by W. B. Barr under Contract #503.

Set granite rock 10" above ground marked with one notch on south edge and three notches on east edge and a cross on top.

Scribed:

- 8" Fir N23½ 40 lks
- 7" Fir N56½W 75 lks
- 5" Fir S54W 13 lks
- 8" Fir S87E 63 lks



Description of corner evidence found:

Found a stone with "+" on top next to aluminum cap marked as shown above.

24" Fir S80E 41' with signs 54-3 and 54-4 attached.

23" Fir N30E 25.4' with signs 54-3 and 54-4 attached.

Description of monument and accessories established to perpetuate the original location of this corner:

Painted scribes red and a 6" red band around all bearing trees.



Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

FILED May 9, 1986  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 6-43-95