


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under GLO contract No. 503 dated May 23, 1884.

Surveyor's General records state:

Set post 4 ft long 4 ins square 24 ins in the ground for cor to secs 28, 29, 32 and 33 marked T 6 S S 28 on the NE, R 44 E S 33 on the SE, S 32 on the SW and S 29 on the NW faces with 1 notch on the S and 4 notches on the E edges from which:



- A tamarack 5 ins diam bears N 87° E, 24 lks dist mkd T 6 S R 44 E S 28 BT
 - A black pine 18 ins diam bears N 3° W 30 lks dist mkd T 6 S R 44 E S 29 BT
 - A black pine 6 ins diam bears S 31° W 15 lks dist mkd T 6 S R 44 E S 32 BT
 - A black pine 12 ins diam bears S 28° E 24 lks dist mkd T 6 S R 44 E S 33 BT
- Description of corner evidence found:


Section 33 bearing tree which is green and in good shape.

A 1 in. iron pipe for corner set by persons unknown.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½ in. brass cap on a 1 in. iron pipe 31 ins. long and projecting 6 ins. out of the ground with a surrounding rock mound.

Brass cap marked as shown: T 6 S R 44 E



CS 1979

I hereby certify that the above corner monument was properly re-established under my supervision on Nov. 2, 1979 and witnessed by Brad Gordon and Jeff Townsend.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

Office of..... County Surveyor Baker County of.....
 State of...Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the...5... day of...November....., 1979
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Nov. 5, 1979
 BAKER COUNTY SURVEYOR
 SURVEY NO. 6-44-5