

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by W. B. Barr under GLO contract no. 503 dated May 23, 1884.

Surveyor's General records state:

Set a granite rock 12 x 8 x 7 ins. 8 ins. in the ground for 1/4 sec cor marked 1/4 on the W side from which:

- A pine 8 ins. diam. bears N 80° W, 95 lks dist. marked 1/4 S BT
- A pine 4 ins. diam. bears S 75° E, 55 lks dist. marked 1/4 S BT




Description of corner evidence found:

None-Corner re-established by single proportionate measure.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 1 inch iron pipe 31 ins. long and projecting 3 ins. out of the ground with a surrounding rock mound.

Brass cap marked thus: T 6 S R 44 E



New bearing trees:

- A fir 14 ins. diam. bears S 86° E, 7.7 ft. dist. marked 1/4 S 33 BT
- A fir 12 ins. diam. bears N 15° W, 35.1 ft. dist. marked 1/4 S 32 BT

Each new bearing tree has a sign 54-3 and a sign 54-4 attached and has a brass washer marked PLS 1639 nailed flush with BT blaze.

I hereby certify that the above corner monument was properly re-established on Nov. 15, 1979, under my supervision and witnessed by Bill Hanley and Tom Fisk.



Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Dec. 12, 1979  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 6-44-9