

NARRATIVE OF SURVEY

A dependent re-survey and partial subdivision of Section 32, T 6 S, R 44 E, W. M., in the Wallowa-Whitman National Forest, Baker County, Oregon.

Bearings based on a solar observation taken on April 26, 1977 for a survey performed for Collins Pine Co. During the course of this survey the north line of Section 5 (identical with the south line of Section 32) was established by survey.

Purpose of Survey

The purpose of this survey was to re-establish the north line of Section 32 and to subdivide the northeast quarter of the said section. Eventually, the individual ownerships of small parcels in the said northeast quarter are to be located and marked on the ground.

Original GLO Survey

The original government survey was performed by W. B. Barr under GLO contract no. 503 dated May 23, 1884.

Method and Procedure for Survey

The survey was begun on Oct. 12, 1979, at which time survey control points for the Collins Pine Co. survey (Survey No. 7-44-11) were recovered. From this control a random traverse was run along the East Eagle Creek Road to the approximate north line of Section 32.

Next, previously identified original government survey corners were searched, examined, remonumented with brass cap monuments and tied to by survey measurements. These corners were the NE corner, the NW corner and the West quarter corner of Section 32 and the West quarter corner of Section 28.

Finally, the obliterated north and east quarter corners were searched for with ^{no} original evidenced being recovered. Subsequently, they were declared lost and re-established with brass cap monuments at their proportioned locations.

Due to winter weather setting in, the field work of the survey was suspended on Nov. 15, 1979, until spring of 1980 at which time the survey is expected to be completed.