


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
NONE-corner established this survey.

P-10



Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½" aluminum cap on 2" aluminum pipe 30" long 25" in ground with 5" proj out of ground with surrounding rock mound and 6' steel fence post alongside with sign 54-9 attached.

Aluminum cap marked as shown in corner diagram.

New bearing trees established:

A tamarack 11 ins dia bears S09°E, 33.8 ft dist mkd CW1/16S21 BT.  
A tamarack 9 ins dia bears S43°E, 41.7 ft dist mkd CW1/16S21 BT.

Each new bearing tree has signs 54-3 and 54-9 attached below a 6" band of red paint and a brass washer marked PLS 1639 nailed flush with BT blaze.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards under my supervision and witnessed by Jim DeMastus and Daryl Schuchardt on July 29, 1985.

Witnessed : Jim DeMastus

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of...County Surveyor..... County of...Baker.....

State of...Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

FILED 4-28-86

BAKER COUNTY SURVEYOR

SURVEY NO. 6-44-25