

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by W.B. Barr under GLO contract No. 503 dated May 23, 1884.

Surveyor General records state:

Set basalt rock 15 x 8 x 5, 10 ins in ground for cor to secs 19, 20, 29 & 30 marked with 2 notches on the S & 5 notches on the E edges from which

- A fir 3 ins dia bears N87°E, 152 lks dist marked T6SR44ES20 BT.
- A fir 4 ins dia bears N85°W, 260 lks dist marked T6SR44ES19 BT.
- A fir 5 ins dia bears S85½°W, 270 lks dist marked T6SR44ES30 BT.
- A fir 6 ins dia bears S22°E, 100 lks dist marked T6SR44ES29 BT.



Description of corner evidence found:

NOTE: Corner position established by survey methods described on accompanying official RECORD OF SURVEY PLAT for dependent resurvey of a portion of T 6 S, R 44 E, W. M.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" aluminum cap on 2" aluminum pipe 30" long 25" in ground with 5" proj. out of ground with surrounding rock mound and 6' steel fence post alongside with sign 54-9 attached.

Aluminum cap marked as shown in corner diagram.

New bearing trees established:

- A fir 16 ins dia bears S13°E, 52.3 ft dist marked T6SR44ES29 BT.
- A fir 10 ins dia bears S40½°W, 63.8 ft dist marked T6SR44ES30 BT.
- A fir 13 ins dia bears N36°W, 62.6 ft dist marked T6SR44ES19 BT.
- A fir 23 ins dia bears N50°E, 86.8 ft dist marked T6SR44ES20 BT.

Each new bearing tree has signs 54-3 and 54-9 attached below a 6 inch band of red paint, and a brass washer marked PLS 1639 nailed flush with BT blaze.

I hereby certify that the above described corner monument was properly established by me and witnessed by Jim DeMastus and Daryl Schuchardt on Aug. 22, 1985.

Witnessed: Jim DeMastus

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of... County Surveyor..... County of... Baker
 State of... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED 4-28-86
BAKER COUNTY SURVEYOR
SURVEY NO. 6-44-30