

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-7

History of original corner establishment:


Corner established by W.B. Barr under GLO contract No. 503 dated May 23, 1884.

Surveyor General records state:

Set basalt rock 10 x 8 x 8, 7 ins in ground for 1/4 sec cor marked 1/4 on the N side from which

A fir 10 ins dia bears S42°W, 26 lks dist marked 1/4S BT.

A fir 11 ins dia bears N80°W, 52 lks dist marked 1/4S BT.



Description of corner evidence found:

NOTE: Corner position established by survey methods described on accompanying official RECORD OF SURVEY PLAT for dependent resurvey of a portion of T 6 S, R 44 E, W. M.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" aluminum cap on 2" aluminum pipe 30" long 25" in ground with 5" proj. out of ground with surrounding rock mound and 6' steel fence post alongside with sign 54-9 attached.

Aluminum cap marked as shown in corner diagram.

New bearing trees established:

A fir 10 ins dia bears S84°W, 67.7 ft dist marked 1/4S29 BT.

A fir 19 ins dia bears N25°E, 3.3 ft dist marked 1/4S20 BT.

Each new bearing tree has signs 54-3 and 54-9 attached below a 6 inch band of red paint, and a brass washer marked PLS 1639 nailed flush with BT blaze.

I hereby certify that the above described corner monument was properly established by me and witnessed by Jim DeMastus and Daryl Schuchardt on Aug. 8, 1985.

Witnessed: Jim DeMastus

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON JULY 14, 1978 WILLIAM L. HANLEY 1639

Office of... County Surveyor... County of... Baker Oregon... State of... I hereby certify that the within instrument was filed in this office for record on the... day of... 19...

... by ... (COUNTY OFFICIAL) (DEPUTY)

FILED 4-28-86 BAKER COUNTY SURVEYOR SURVEY NO. 6-44-31