

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-7

History of original corner establishment:

Corner established by W. B. Barr under GLO contract No. 503 dated May 23, 1884.


Surveyor's General records state:

Set slatestone 18 x 16 x 6, 12 ins in the ground for 1/4 on the N side from which:

- A pine 7 ins dia bears S74°W, 70 lks dist mkd 1/4S BT.
- A pine 6 ins dia bears N85°E, 67 lks dist mkd 1/4S BT.

Corner REESTABLISHED by James D. Hanley on Nov. 14, 1979.....Set a 2 1/2" brass cap on a 1" iron pipe 31" long and projecting out of ground with a surrounding rock mound, as shown in corner diagram, from which:

- A fir 20 ins dia bears S21°W, 74.2 ft dist mkd 1/4S32 BT.
- A pine 8 ins dia bears N76°E, 44.7 ft dist mkd 1/4S29 BT.



Description of corner evidence found:

Found brass cap on iron pipe as shown in corner diagram.

- A fir 21 ins dia bears S21°W, 74.2 ft dist mkd 1/4S32 BT.
- A pine 11 ins dia bears N76°E, 44.7 ft dist mkd 1/4S29 BT.

Description of monument and accessories established to perpetuate the original location of this corner:

Improved surrounding rock mound around corner monument and set a 6 foot steel fence post alongside with a sign 54-9 attached.

Each original bearing tree has signs 54-3 and 54-9 attached below a 6 ins band of red paint.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards under my supervision and witnessed by Jim DeMastus and Daryl Schuchardt on Sept. 25, 1984.

Witnessed : Jim DeMastus

REGISTERED PROFESSIONAL LAND SURVEYOR

*William L. Hanley*

OREGON JULY 14, 1978 WILLIAM L. HANLEY 1639

Office of County Surveyor..... County of Baker.....  
State of Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

FILED 4-28-86  
BAKER COUNTY SURVEYOR  
SURVEY NO. 6-44-43