

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z-13

History of original corner establishment:

Corner established by W. B. Barr under GLO contract no. 503 dated May 23, 1884.

Surveyor General records state:

Set post 4 ft long 4 ins diam 24 ins in ground for corner to Secs 3, 4, 33 & 34 marked T6SR44E S34 on the NE, T7SR44E S3 on the SE, S4 on the SW, S33 on the NW faces with 3 notches on the E & W faces from which:

- A black pine 18 ins diam bears N 70 $\frac{1}{2}$ ° E, 17 lks dist marked T6SR44ES34BT
- A black pine 15 ins diam bears S 15° E, 19 lks dist marked T7SR44ES3BT
- A black pine 10 ins diam bears S 23° W, 8 lks dist marked T7SR44ES4BT
- A black pine 12 ins diam bears N 59° W, 4 lks dist marked T6SR44ES33BT

DIAGRAM

T 6 S R 44 E	
S 33	S 34
S 4	S 3
T 7 S	
1984	
ORLS 1639	

Description of corner evidence found:

Found full record scribes on partially decomposed remains of portions of sections 3 and 4 bearing trees. No trace of sections 33 and 34 bearing trees or of original wooden post.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 $\frac{1}{2}$ inch aluminum cap on a 2 inch aluminum pipe 30 inches long, 25 inches in the ground with 5 inches projecting out of the ground with a surrounding rock mound and a 6 foot steel fence post alongside with a sign 54-9 attached.

Aluminum cap marked as shown in corner diagram.

New bearing trees established:

- A pine 10 ins diam bears S 59 $\frac{1}{2}$ ° W, 49.2 ft dist marked T7SR44ES4 BT
- A fir 10 ins diam bears N 45° W, 47.2 ft dist marked T6SR44ES33 BT
- A fir 12 ins diam bears N 29 $\frac{1}{2}$ ° E, 13.6 ft dist marked T6SR44ES34 BT
- A fir 14 ins diam bears S 12° E, 6.4 ft dist marked T7SR44ES3 BT

Each new bearing tree has a brass washer marked PLS 1639 nailed flush with BT blaze and has signs 54-3 and 54-9 attached below a 6 inch band of red paint around.

I hereby certify that the above described corner monument was properly established by me and witnessed by Jim DeMastus and Daryl Schuchardt on Oct. 24, 1984.

Jim DeMastus

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

**OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639**

Office of..... Surveyor..... County of..... Baker.....
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by.....
(COUNTY OFFICIAL) (DEPUTY)

FILED 4-28-86
BAKER COUNTY SURVEYOR
6-44-68