

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

DIAGRAM

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:


1/4 Corner of Sections 21/28

William B. Barr, August 30, 1884:

Set a granite rock 12 X 10 X 7, 8 ins. in the ground, marked 1/4 on N. side, from which:

A Black Pine, 15 ins. in diam., bears N 22°E, 14 lks. dist. marked 1/4 S.BT.

A Black Pine, 15 ins. in diam., bears S 25°E, 47 lks. dist. Marked 1/4 S.BT.



William L Hanley, ORLS No. 1639, 1985

Found:

Marked Stone of record dimensions

A Windblow bears N 22°E, 14 lks. dist., with no visible scribes in rotten wood

A Root-hole bears S 25°E, 47 lks. dist.

Set:

A 2 1/2 ins. Aluminum Cap on 2 ins. Aluminum pipe 30 ins. long 25 ins. in ground with surrounding rock mound and 6 ft. steel fence post alongside with sign 54-9 attached.

Buried marked stone monument alongside.

New BT's:

A Fir, 10 ins. in diam., bears N 34°W, 20.8 ft. dist. marked 1/4 S.21 BT.

A Fir, 12 ins. in diam., bears S 78°W, 18.5 ft. dist. marked 1/4 S.28 BT.

Attached 54-3 and 54-9 signs to both BT's, with brass washer marked PLS 1639 nailed flush with BT blaze.

DESCRIPTION OF CORNER EVIDENCE FOUND:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

Found: 2 1/2 ins. Aluminum Cap, on 2 ins. Aluminum Pipe. per Baker County Surveyor's File No. 6-44-33, marked as shown.

A Fir, 13 ins. in diam.(with dead top), bears S 75°W, 18.5 ft. dist. with visible scribe.

A Fir, 11 ins. in diam. (dead), bears N 34°W, 20.8 ft. dist.

S Steel Fence post W/LSM sign bears North 3 ft.+/-.

K-tags on large firs in NE & NW quadrants.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:

New BT's:

A Fir, 19 ins. in diam., bears N 41°E, 41.7 ft. dist. marked 1/4 S.21 BT.

A Larch, 18 ins. in diam., bears S 2°W, 27.8 ft. dist. marked 1/4 S.28 BT.

A Spruce, 12 ins. in diam., bears S 39°W, 33.9 ft. dist. marked 1/4 S.28 BT.

A Fir, 12 ins. in diam., bears N 54°W, 25.9 ft. dist. marked 1/4 S.21 BT.

All BT's fixed with BT tag, LSM sign, Washer W/LS No. 2367

CORNER MONUMENT REFERENCES:

I, Robert C. Lamburth certify that this corner was Properly re-established in 1984 and maintained on 6/26/08, as witnessed by K. Erich Shrack, LSIT

FILED October 27, 2008
BAKER COUNTY SURVEYOR
SURVEY NO. 6-44-72
CORNER PRES. NO. 116

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert C. Lamburth
10/22/08

OREGON
July 28, 1988
ROBERT C. LAMBURTH
2367