

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

DIAGRAM

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

1/4 Corner of Sections 29/28

William B. Barr, August 29, 1884:

Set a volcanic rock 20 X 6 X 5, 15 ins. in the ground,
marked 1/4 on the W. side, from which:

A Black Pine, 8 ins. in diam., bears S 59°W, 27 lks. dist. marked 1/4 S.BT.

A Black Pine, 6 ins. in diam., bears N 87°E, 31 lks. dist. marked 1/4 S.BT.

William L Hanley, ORLS No. 1639, 1979

Found:

A stone 19 X 7 X 7 ins. firmly set with 1/4 marked on N. Face

A Lodgepole Pine, dead and standing, 14 ins. in dia., marked 1/4 S.BT for Section 29 BT.

A Pine, downed and rotting, 12 ins. in dia., with BT visible for Section 28 BT.

Set:


A 2 1/2 ins. Brass Cap on 1 ins. Iron pipe 31 ins. long 25 ins. in ground with
surrounding rock mound.

New BT's:

A Fir, 9 ins. in diam., bears S 76°W, 18.9 ft. dist. marked 1/4 S.29 BT.

A Fir, 10 ins. in diam., bears S 51°E, 31.2 ft. dist. marked 1/4 S.28 BT.

Attached 54-3 sign to both BT's, with brass washer marked PLS 1639
nailed flush with BT blaze.



DESCRIPTION OF CORNER EVIDENCE FOUND:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

Found: 2 ins. Brass Cap, on 1 ins. IP. per Baker County Surveyor's File No. 6-44-8,
marked as shown.

A Fir, 18 ins. in diam., bears S 51°E, 31.2 ft. dist., with healed blaze.

A Fir, 15 ins. in diam., bears S 76°W, 18.9 ft. dist., with healed blaze.

K-tags in SW & NW quadrants.

Witness post bears East, 3 ft. ±.

Property Boundary post bears West 10 ft. ±.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO
PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:**

New BT's:

Repainted existing BT's

A Pine, 24 ins. in diam., bears N 8°W, 46.9 ft. dist. marked 1/4 S.29 BT.

A Larch, 28 ins. in diam., bears S 6°E, 82.8 ft. dist. marked 1/4 S.28 BT.

CORNER MONUMENT REFERENCES:

I, Robert C. Lamburth certify that this corner was
Properly re-established in 1979 and maintained on
7/02/08, as witnessed by K. Erich Shrack LSIT

FILED October 29 2008
BAKER COUNTY SURVEYOR
SURVEY NO. 6-44-93
CORNER PRES. NO. 117

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert C. Lamburth
10/22/08

OREGON
July 28, 1988
ROBERT C. LAMBURTH
2367