

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**DIAGRAM**

**HISTORY OF ORIGINAL CORNER ESTABLISHMENT:**

**C-W 1/16 Corner of Section 28**  
No Original Record

**William L Hanley, ORLS No. 1639, 1985**

Set:

A 2 1/2 ins. Aluminum Cap on 2 ins. Aluminum pipe 31 ins. long 27 ins. in ground with surrounding rock mound and 6 ft. steel fence post alongside with 54-4 sign attached.

Establish BT's:

A Pine, 7 ins. in diam., bears N 71/2°E, 122.1 ft. dist. marked CW 1/16 S.28 BT.

A Pine, 9 ins. in diam., bears N 34°E, 114.5 ft. dist. marked CW 1/16 S.28 BT.

Attached 54-3 sign to both BT's, with brass washer marked PLS 1639 nailed flush with BT blaze.

**DESCRIPTION OF CORNER EVIDENCE FOUND:**

**Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008**

The BLM's repositioning of the South 1/4 Corner of Section 28 warrants a new section subdivision, therefore:

The position of the 2 1/2 ins. Aluminum Cap set by ORLS No. 1639 bears S 89°28'10"W, 169.16 ft. dist. from new position. I therefore sawed off the existing monument below ground level, destroyed the marks on the bearing trees, removed all signs and tags and painted over the blazes and existing red paint with black paint.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:**

**Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008**

Set Monument at new breakdown position:

A standard 3 1/4 ins. USDA Aluminum Monument, 30 ins. long, 24 ins. in the ground, marked as shown, from which:

A Fir, 24 ins. in diam., bears S 50°E, 32.4 ft. dist., scribed CW 1/16 S28 BT

A Fir, 12 ins. in diam., bears S 11°W, 11.3 ft. dist., scribed CW 1/16 S28 BT

A 6 ft. steel post W/LSM and Property boundary sign bears South 5 ft.+/-.

A 6 ft. steel post with Property boundary sign bears West 5 ft.+/-.



**CORNER MONUMENT REFERENCES:**

I, Robert C. Lamburth certify that this corner was Properly established on 7/16/08, as witnessed by K. Erich Shrack, LSIT

FILED OCTOBER 27, 2008  
BAKER COUNTY SURVEYOR  
SURVEY NO. 6-44-74  
CORNER PRES. NO. 118

