

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

DIAGRAM

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:


1/4 Corner of Sections 28/27

William B. Barr, August 26, 1884:

A fir 5 ins. in dia., for 1/4 Sec. Cor., marked 1/4 S on the W. side, from which:

A Tamarack, 10 ins. in diam., bears N 39°W, 15 lks. dist. marked 1/4 S.BT.

A Fir, 4 ins. in diam., bears S 86°E, 25 lks. dist. marked 1/4 S.BT.



William L Hanley, ORLS No. 1639, 1985

Found:

No original evidence found

Set: At single proportion position:

A 2 1/2 ins. Aluminum Cap on 2 ins. Aluminum pipe 30 ins. long 16 ins. in ground to bedrock with surrounding rock mound and 6 ft. steel fence post alongside with sign 54-9 attached.

New BT's:

A Fir, 15 ins. in diam., bears N 58°E, 17.9 ft. dist. marked 1/4 S.27 BT.

A Fir, 9 ins. in diam., bears N 03°30'W, 43.5 ft. dist. marked 1/4 S.28 BT.

Attached 54-3 and 54-9 signs to both BT's, with brass washer marked PLS 1639 nailed flush with BT blaze.

DESCRIPTION OF CORNER EVIDENCE FOUND:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

Found: 2 1/2 ins. Aluminum Cap, on 2 ins. Aluminum Pipe in rock mound. per Baker County Surveyor's File No. 6-44-41, marked as shown.

A Dead Fir bears N 58°E, 17 ft. dist., with healed blaze.

A Fir, 13 ins. in diam., bears N 03°30'W, 43.5 ft. dist., with healed blaze.

Reset Witness post, East, 3 ft. +/-, Repainted existing BT's

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

New BT's:

A Fir, 18 ins. in diam., bears S 88°E, 28.5 ft. dist. marked 1/4 S.27 BT.

A Pine, 36 ins. in diam., bears S 14°W, 47.7 ft. dist. marked 1/4 S.28 BT.

A Pine, 30 ins. in diam., bears S 40°W, 50.8 ft. dist. marked 1/4 S.28 BT.

CORNER MONUMENT REFERENCES:

I, Robert C. Lamburth certify that this corner was Properly re-established in 1985 and maintained on 7/01/08, as witnessed by K. Erich Shrack, LSIT

FILED OCTOBER 27, 2008
BAKER COUNTY SURVEYOR
SURVEY NO. 6-44-76
CORNER PRES. NO. 120

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert C. Lamburth
10/22/08

OREGON
July 28, 1988
ROBERT C. LAMBURTH
2367