

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

DIAGRAM

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

Corner of Sections 28, 29, 32 & 33

William B. Barr, August 26, 1884:

Set a post 4 ft. long, 4 ins. diam., 24 ins. in the ground, for cor. to Secs. 28, 29, 32 & 33, marked T6S S28 on NE, R44E S33 on the SE, S32 on the SW and S29 on the NW faces, with 1 notch on the S. and 4 notches on the E. edges from which:

- A Tamarack, 5 ins. in diam., bears N 87°E, 24 lks. dist. marked T6S R44E S28 BT.
- A Black Pine, 18 ins. in diam., bears N 3°W, 30 lks. dist. marked T6S R44E S29 BT.
- A Black Pine, 6 ins. in diam., bears S 31°W, 15 lks. dist. marked T6S R44E S32 BT.
- A Black Pine, 12 ins. in diam., bears S 28°E, 24 lks. dist. marked T6S R44E S33 BT.

James D. Hanley, ORLS No. 1206, 1979

Found: Section 33 Bearing Tree which is green and in good shape

A 1 ins. Iron pipe for corner set by persons unknown.

Set: A 2 1/2 ins. Brass Cap on 1 ins. Iron pipe 31 ins. long and projecting 6 ins. out of the ground with a surrounding rock mound.

William L Hanley, ORLS No. 1639, 1985

Found: A 2 1/2 ins. Brass Cap on 1 ins. Iron pipe in small rock mound per survey no. 6-44-5

Improved surrounding rock mound around corner monument and set a

6 ft. steel fence post alongside with sign 54-9 attached.

New BT's:

- A Tamarack, 7 ins. in diam., bears N 69°W, 32.7 ft. dist. marked T6S R44E S.29 BT.
 - A Fir, 14 ins. in diam., bears N 06°E, 32.3 ft. dist. marked T6S R44E S.28 BT.
 - A Fir, 9 ins. in diam., bears S 44°E, 15.2 ft. dist. marked T6S R44E S.33 BT.
 - A Tamarack, 8 ins. in diam., bears S 10°W, 77.4 ft. dist. marked T6S R44E S.32 BT.
- Attached 54-3 and 54-9 signs to both BT's, with brass washer marked PLS 1639 nailed flush with BT blaze.

BLM, Lawrence D. Holmes, 1988

Found: The cor. of secs. 28, 29, 32 and 33, perpetuated and recorded by James D. Hanley, Registered Land Surveyor No. 1206, in 1979, monumented with an iron pipe, 1 in. diam., firmly set, projecting 4 ins. above ground, with brass cap marked as shown: from which the remains of an original bearing tree:

A lodgepole pine snag, 9 ins. diam., bears S.28°E, 24 lks. dist., with scribe marks T6S R44E S33 visible on partially healed blaze.

And bearing trees marked by Hanley:

- A fir, 13 ins. diam., bears N.16°E, 48.5 lks. dist., with scribe marks T6S R44E S28 BT visible on partially healed blaze. (Note BLM error in notes, tree should be N06°E)
- A fir, 8 ins. diam., bears S.44°E, 23 lks. dist., with scribe marks T6S R44E S33 BT visible on partially healed blaze.
- A fir, 9 ins. diam., bears S.10°W, 117 lks. dist., with scribe marks T6S R44E S32 BT visible on partially healed blaze.
- A Larch, 8 ins. diam., bears N.69°W, 51 lks. dist., with scribe marks T6S R44E S29 BT visible on partially healed blaze.

DESCRIPTION OF CORNER EVIDENCE FOUND:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

Found:

A 2 1/2 ins. Brass Cap on 1 ins. Iron pipe in small rock mound, per Baker County Surveyor's File No. 6-44-5, marked as shown.

A Fir, 14 ins in diam., bears S 44°E, 15.2 ft. dist.

GLO pine stump is wired to this tree.

A Larch, 15 ins. in diam., bears N 69°W, 32.7 ft. dist., with healed blaze.

A Fir, 25 ins. in diam., bears N 6°E, 32.3 ft. dist., with healed blaze.

Steel fence post bears North, 3 ft. +/- K-tag on 8 ins. fir in SW quadrant.

