

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**HISTORY OF ORIGINAL CORNER ESTABLISHMENT:**

**DIAGRAM**

**1/4 Corner of Sections 28/33**

**William B. Barr, August 26, 1884:**

Set a Slate stone 22 X 10 X 5 ins., 17 ins. in the ground for 1/4 Sec. Cor., marked 1/4 on N. side, from which:

A Fir, 5 ins. in diam., bears N 33°W, 12 lks. dist. marked 1/4 S.BT.

A Fir, 6 ins. in diam., bears S 6°E, 13 lks. dist. marked 1/4 S.BT.

**William L. Hanley, ORLS No. 1639, 1985**

Found: No original evidence found

Set: At single proportion position

A 2 1/4 ins. Aluminum Cap on 2 ins. Aluminum pipe 30 ins. long 25 ins. in ground with surrounding rock mound and 6 ft. steel fence post alongside with sign 54-9 attached.

New BT's:

A Fir, 8 ins. in diam., bears S 44°E, 21.1 ft. dist. marked 1/4 S.33 BT.

A Fir, 10 ins. in diam., bears N 16°30'E, 35.2 ft. dist. marked 1/4 S.28 BT.

Attached 54-3 and 54-9 signs to both BT's, with brass washer marked PLS 1639

nailed flush with BT blaze.

**BLM, Lawrence D. Holmes, 1988**

Found: At the position as attested to by Mr. Larry L. Cribbs:

A rotted out fir snag, 25 ins. diam., 15 ft. high, bears N.33°W, 12 lks. dist., no marks visible.

Set: A stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap mkd. as shown from which new bearing trees:

A Fir, 15 ins. diam., bears N 15°E., 55.5 lks. dist., mkd. 1/4 S28 BT

A Fir, 6 ins. diam., bears S 28°E, 3.5 lks. dist., mkd. 1/4 S33 BT.

Deposit a Deep-1 magnetic marker at base and a steel fence post alongside the stainless steel post.

(Calculated position of Corner established by William L. Hanley bears N 89°22'W, 10.27 chs. dist.)

**DESCRIPTION OF CORNER EVIDENCE FOUND:**

**Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008**

Found :3 1/4 ins. Brass Cap, on 2 ins. Stainless Steel post., marked as shown.


A Fir, 32 ins. in diam., bears N 15°E, 36.6 ft. dist., with healed blaze.

A Fir, 14 ins. in diam., bears East, 11.3 ft. dist., with healed blaze.

(There is no record of this tree being used as a BT)

A Fir, 9 ins. in diam., bears S 28°E, 2.3 ft. dist., with healed blaze.

Corner established by William L. Hanley bears N 89°21'06"W, 677.23 ft. dist.,



**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:**

New BT's:

A Fir, 9 ins. in diam., bears N 40°E, 22.8 ft. dist. marked 1/4 S.28 BT.

Repainted existing BT's, Attached BT tags and LSM signs where needed.

Reset Witness posts, North, 1 ft. +/-, and East, 1 ft. +/-.

The position of the 2 1/2 ins. Aluminum Cap set by ORLS No.1639 bears N 89°21'06"W, 677.23 ft.

dist. from the BLM position. I therefore sawed off the existing monument below ground level,

destroyed the marks on the bearing trees, removed all signs and tags and painted over the blazes and

existing red paint with black paint.

**CORNER MONUMENT REFERENCES:**

I, Robert C. Lamburth certify that this corner was Properly re-established in 1988 and maintained on 6/28/08, as witnessed by K. Erich Shrack, LSIT

FILED OCTOBER 27, 2008  
BAKER COUNTY SURVEYOR  
SURVEY NO. 6-44-79  
CORNER PRES. NO. 123

