

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

DIAGRAM

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

NW 1/16 Corner of Section 33
No Original Record

William L Hanley, ORLS No. 1639, 1985

Set:

A 2 1/2 ins. Aluminum Cap on 2 ins. Aluminum pipe 31 ins. long 25 ins. in ground with surrounding rock mound and 6 ft. steel fence post alongside with 54-4 sign attached.

Establish BT's:

A Fir, 14 ins. in diam., bears N 66°E, 135.1 ft. dist. marked NW1/16 S.33 BT.

A Fir, 8 ins. in diam., bears S 45°E, 39.9 ft. dist. marked NW1/16 S.33 BT.

Attached 54-3 and 54-9 signs to both BT's, with brass washer marked PLS 1639 nailed flush with BT blaze.

DESCRIPTION OF CORNER EVIDENCE FOUND:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

The BLM's repositioning of the North 1/4 Corner of Section 33 warrants a new section subdivision, therefore:

The position of the 2 1/2 ins. Aluminum Cap set by ORLS No.1639 bears N 89°58'09"W, 253.25 ft. dist from new position. I therefore sawed off the existing monument below ground level, destroyed the marks on the bearing trees, removed all signs and tags and painted over the blazes and existing red paint with black paint.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:


Set Monument at new breakdown position:

A standard 3 1/4 ins. USDA Aluminum Monument, 30 ins. long, 24 ins. in the ground, marked as shown, from which:

A Fir, 21 ins. in diam., bears S 74°W, 41.32 ft. dist., scribed NW 1 1/16 S33 BT

A Fir, 25 ins. in diam., bears N 50°W, 61.78 ft. dist., scribed NW 1 1/16 S33 BT

Set a steel post with LSM sign East 1.4 ft. ±.



CORNER MONUMENT REFERENCES:

I, Robert C. Lamburth certify that this corner was Properly established on 7/24/08, as witnessed by K. Erich Shrack, LSIT

FILED OCTOBER 27 2008
BAKER COUNTY SURVEYOR
SURVEY NO. 6-44-80
CORNER PRES. NO. 124

