

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

DIAGRAM

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:


C-E 1/16 Corner of Section 32
No Original Record

William L Hanley, ORLS No. 1639, 1980

Set:
A 5/8 ins. X 30 ins. Rebar.

William L Hanley, ORLS No. 1639, 1985

Found: A 5/8 ins. X 30 ins. Rebar with a yellow plastic cap marked RPE 2808
Set: A 2 1/2 ins. Brass Cap on 2 ins. Iron pipe
A Pine, 8 ins. in diam., bears S 09°W, 21.3 ft. dist., marked CE 1/16 S32 BT
A Fir, 12 ins. in diam., bears S 77°W, 18.9 ft. dist. marked CE 1/16 S32 BT
Ref: East - Eagle Cadastral Survey, 1985.



DESCRIPTION OF CORNER EVIDENCE FOUND:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

Found:
A 2 1/2 ins. Brass Cap on 2 ins. Iron pipe, stamped as shown.
from which:
A Fir, 20 ins. in diam., bears S 77°W, 18.9 ft. dist., with healed blaze
A Pine snag, 8 ins. in diam., bears S 9°W, 21.3 ft. dist.
A steel post W/LSM and property boundary signs bears West 3 ft +/-.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

New BT's
A Fir, 13 ins. in diam., bears S 6 1/2°E, 36.3 ft. dist., scribed CE 1/16 S32 BT
A Fir, 9 ins. in diam., bears N 21°E, 8.1 ft. dist., scribed CE 1/16 S32 BT
A Fir, 19 ins. in diam., bears N 1°W, 24.8 ft. dist., scribed CE 1/16 S32 BT

CORNER MONUMENT REFERENCES:

I, Robert C. Lamburth certify that this corner was Properly established in 1985 and maintained on 10/18/07, as witnessed by K. Erich Shrack, LSIT

FILED OCTOBER 27, 2008
BAKER COUNTY SURVEYOR
SURVEY NO. 6-44-81
CORNER PRES. NO. 125

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert C. Lamburth
10/22/08

OREGON
July 28, 1988
ROBERT C. LAMBURTH
2367