

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

DIAGRAM

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:


1/4 Corner of Sections 32/33

William B. Barr, August 29, 1884:

Set a granite rock 12 X 8 X 7 ins., 8 ins. in the ground,
marked 1/4 on the W. side, from which:

A Pine, 8 ins. in diam., bears N 80°W, 95 lks. dist. marked 1/4 S.BT.

A Pine, 11 ins. in diam., bears S 75°E, 55 lks. dist. marked 1/4 S.BT.



James D. Hanley, ORLS No. 1206, 1979

Found:

No Original Evidence found

Set: At the single proportion position:

A 2 1/2 ins. Brass Cap on 1 ins. Iron pipe 31 ins. long 27 ins. in ground with
surrounding rock mound.

New BT's:

A Fir, 14 ins. in diam., bears S 86°E, 7.7 ft. dist. marked 1/4 S.33 BT.

A Fir, 12 ins. in diam., bears N 15°W, 35.1 ft. dist. marked 1/4 S.32 BT.

Attached 54-3 and 54-4 signs to both BT's, with brass washer marked PLS 1639
nailed flush with BT blaze.

DESCRIPTION OF CORNER EVIDENCE FOUND:

Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008

Found:

2 ins. Brass Cap, on 1 ins. IP. per Baker County Surveyor's File No. 6-44-9,
marked as shown.

A Fir, 24 ins. in diam., bears S 86°E, 26.7 ft. dist., with healed blaze.

(Note: The distance on J.D. Hanley's cor. cert., is incorrectly shown as 7.7 ft.)

A Fir, 23 ins. in diam., bears N 15°E, 34.2 ft. dist., with healed blaze.

(Note: The bearing on J.D. Hanley's cor. cert., is incorrectly shown as N 15°W)

K-tags in SW & NW quadrants.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO
PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:**

New BT's:

Repainted existing BT's

A Fir, 11 ins. in diam., bears S 77°W, 36.8 ft. dist. marked 1/4 S.32 BT.

A Fir, 21 ins. in diam., bears N 65°W, 52.5 ft. dist. marked 1/4 S.32 BT.

CORNER MONUMENT REFERENCES:

**I, Robert C. Lamburth certify that this corner was
Properly re-established in 1979 and maintained on
10/16/07, as witnessed by K. Erich Shrack, LSIT**

FILED OCTOBER 27, 2008
BAKER COUNTY SURVEYOR
SURVEY NO. 6-44-82
CORNER PRES. NO. 126

