

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**


**DIAGRAM**

**HISTORY OF ORIGINAL CORNER ESTABLISHMENT:**

**1/4 Corner of Sections 33/34**

**William B. Barr, August 26, 1884:**

- A fir 6 ins. in dia., for 1/4 Sec. Cor., marked 1/4 S on the W. side, from which:
- A Fir, 5 ins. in diam., bears N 25°W, 25 lks. dist. marked 1/4 S.BT.
- A Fir, 15 ins. in diam., bears S 15°E, 15 lks. dist. marked 1/4 S.BT.



**William L Hanley, ORLS No. 1639, 1985**

Found:

No original evidence found

Set: At single proportion position

A 2 1/2 ins. Aluminum Cap on 2 ins. Aluminum pipe 30 ins. long 25 ins. in ground with surrounding rock mound and 6 ft. steel fence post alongside with sign 54-9 attached.

New BT's:

- A Fir, 8 ins. in diam., bears S 24°E, 8.7 ft. dist. marked 1/4 S.34 BT.
- A Fir, 10 ins. in diam., bears N 83°30'W, 16.5 ft. dist. marked 1/4 S.33 BT.
- Attached 54-3 and 54-9 signs to both BT's, with brass washer marked PLS 1639 nailed flush with BT blaze.

**DESCRIPTION OF CORNER EVIDENCE FOUND:**

**Robert C. Lamburth, ORLS No. 2367, Glahe & Assoc., 2008**

Found: 2 1/2 ins. Aluminum Cap in mound of stone, marked as shown.

A Fir, 13 ins. in diam., bears S 24°E, 8.7 ft. dist., with healed blaze.

A Rotting Fir, 15 ins. in diam., bears N 83°30'W, 16.5 ft. dist., some scribe visible.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THE CORNER:**

Reset Witness post, Southwest, 2 ft. +/-

Repainted existing BT's

New BT's:

- A Fir, 24 ins. in diam., bears N 68°E, 16.4 ft. dist. marked 1/4 S.34 BT.
- A Fir, 15 ins. in diam., bears S 71°W, 28.9 ft. dist. marked 1/4 S.33 BT.
- A Fir, 16 ins. in diam., bears N 31°W, 61.2 ft. dist. marked 1/4 S.33 BT.

**CORNER MONUMENT REFERENCES:**

I, Robert C. Lamburth certify that this corner was Properly re-established in 1984 and maintained on 6/30/08, as witnessed by K. Erich Shrack, LSIT

FILED OCTOBER 27, 2008  
BAKER COUNTY SURVEYOR  
SURVEY NO. 6-44-84  
CORNER PRES. NO. 128

