

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by W. B. Barr under GLO contract no. 503 dated May 23, 1884.

Surveyor's General records state:

Set a granite rock 15 x 10 x 4 ins. 10 ins in the ground marked 1/4 on the N side; from which:

A fir 12 ins. diam. bears N 06° W, 16 lks. dist. marked 1/4 S BT
A fir 6 ins. diam. bears S 18° E, 35 lks. dist. marked 1/4 S BT



Description of corner evidence found:

James D. Hanley, County Surveyor for Baker County, made survey measurements to a brass cap on a 2 inch iron pipe in 1962 and again in 1964. In 1974 it was discovered that the corner monument had been destroyed, however, survey control points of the 1962 and 1964 surveys were recovered.

The corner was re-established from the basis of these survey control points.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 3 in. brass disc in a concrete post 6 ins. square and 34 ins. long projecting 4 ins. out of the ground with a surrounding rock mound and a 6 foot steel fence post alongside with a sign 54-4 attached.


Brass cap marked thus: T 6 S R 45 E

1	S 27
4	S 34
CS 1979	

New bearing tree:

A fir 14 ins. diam. bears N 29° W, 53.2 ft. dist. marked 1/4 S 27 BT and has a sign 54-3 attached below a band of red paint and has a brass washer marked PLS 1639 nailed flush with the BT blaze.

I hereby certify that the above corner monument was properly re-established under my supervision on Nov. 7, 1979 and witnessed by Bill Hanley and Jeff Townsend.



Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-5/ (9/71)

FILED Dec. 11, 1979
 BAKER COUNTY SURVEYOR
 SURVEY NO. 6-45-14