

Dependent Resurvey of a Portion of the Subdivisional Lines,  
T. 6 S., R. 45 E., Willamette Meridian, Oregon

FEET

|       |        |
|-------|--------|
| T 6 S | R 45 E |
| S 9   | S 10   |
| S 16  | S 15   |

2004

from which

A subalpine fir, 19 ins. diam., bears N. 23 $\frac{3}{4}$ ° E., 56.6 ft. dist., mkd. T6S R45E S10 BT.

The marks BXO, on a basalt boulder, 4 x 3 x 1 ft. high, bear S. 45 $\frac{1}{4}$ ° E., 22.3 ft. dist.

A subalpine fir, 13 ins. diam., bears S. 13 $\frac{1}{2}$ ° W., 75.1 ft. dist., mkd. T6S R45E S16 BT.

A subalpine fir, 10 ins. diam., bears N. 29° W., 58.4 ft. dist., mkd. T6S R45E S9 BT.

Deposit a magnet in a white plastic case at the base of the stainless steel post.

Corner is located on steep W. slope, in scattered timber.

The geographic position (NAD 1983 (98)) of this corner is:

Latitude: 45° 03' 05.717" N.      Longitude: 117° 12' 14.690" W.

From the cor. of secs. 10, 11, 14, and 15, remonumented in 1982, by Duane I. Griffith, Professional Land Surveyor No. 644, and filed as Survey No. 6-45-75 at the office of the Baker County Surveyor in Baker City, Oregon, monumented with an aluminum post, 2 $\frac{1}{2}$  ins. diam., firmly set, projecting 8 ins. above the ground, in a mound of stone, 4 ft. base, to top, with aluminum cap mkd.

BAGETT GRIFFITH &amp; ASSOC

|       |        |
|-------|--------|
| T 6 S | R 45 E |
| S 10  | S 11   |
| S 15  | S 14   |

1982

OPLS 644

from which the original bearing tree

A fir, 28 ins. diam., bears S. 45° E., 89.8 ft. dist., with illegible scribe marks visible on partially opened blaze. (Record, S. 38° E., 99.0 ft.)