


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

45° 01' 45.820" N  
117° 11' 44.983" W  
+/- 5 Meters.  
NAD 83



**History of original corner establishment:**

Duane Griffith, PLS 644, 1982

Set: Chiseled an X on west face of rock outcrop from which:

A red fir, 16 ins. diam., bears N 58° E 25.2 ft. marked C 1/4 S22 BT.

A red fir, 18 ins. diam., bears S 59° E 12.1 ft. marked C 1/4 S22 BT.

A 2 1/2 x 30 in. aluminum pipe 24 ins. in the ground, bears S 28° E 11.2 ft. from the true corner point as a reference monument.

Raised a mound of stone around the RM. Set a steel fence post approx. 5 ft. easterly.

Phillip G. Griffin, Cadastral Surveyor, 1992

Set: A stainless steel post, 28 ins. long, 2 1/2 ins. diam., 18 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap from which:

A rock tower, 10 x 10 x 10 ft high, bears S 37° E 16 lks. (10.6 ft.) to the marks BXO at the NW corner.

A crooked Douglas fir, 22 ins. diam., bears N 36° W 33 lks., (21.8 ft.) to the base, marked C 1/4 S22 BT.

From this point, a point established as the C 1/4 S22 by Duane Griffith, Registered Land Surveyor No. 644, in 1982, and filed with the Baker County Surveyor under survey No. 6-45-31 bears N 12° 24' 00" E 1.7 chains (112.2 ft.). This point was established using erroneous control and is not utilized in this survey; monumented by a cross on a rock ledge from which:

A fir, 18 ins. diam., bears N 58° E 38 lks. (25.1 ft.) with scribe marks C 1/4 S22 BT on open blaze.

An aluminum post, 2 1/2 ins. diam., firmly set, projecting 8 ins. above ground., for a reference monument, bears S 28° E 17 lks. with aluminum cap marked Bagett Griffith & Assoc. RM 11.2 T6S R45E S22 C 1/4 1982 OPLS 644 and an arrow pointing to the corner. A steel fencepost is alongside the reference monument.

A fir, 20 ins. diam., bears S 59° E 18 lks. (11.9 ft.) with scribe marks E 1/4 S22 BT visible on an open double blaze.

Equipment: Warren Knight staff compass with tripod, Var. 15 1/2° E,

Keson tape, clinometer, loggers tape

Crew: Richard Chesebro & Ron Grace

Date: August 9, 2008

Office of.....County.....Surveyor..... County of.....Baker.....  
State of.....Oregon....., I hereby certify that the within was filed  
in this office for record on the..... day of....., 20.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

1/9/09  
REGISTERED PROFESSIONAL LAND SURVEYOR

Richard Chesebro  
OREGON  
JULY 18, 1980  
Richard A. Chesebro  
1886

Renews: 12-31-2009

FILED JAN. 14, 2009  
BAKER COUNTY SURVEYOR  
SURVEY NO. 6-45-159