


Land Surveying &  
Boundary Consulting

32610 Mountain Lakes Drive  
Klamath Falls, OR 97601  
(541) 356-2381

**CERTIFIED RECORD OF LAND**  
**CORNER MONUMENTATION**

45° 01' 21.324" N  
117° 11' 18.529" W  
+/- 5 Meters.  
NAD 83



**History of original corner establishment:**

**W.B. Barr, GLO, 1884**

Set: A granite rock, 12 x 12 x 4 ins. 8 ins. in the ground marked with 2 notches on the S and E edges from which:

- A fir, 6 ins. diam., bears N 88° E 48 lks. (31.7 ft.) marked T6S R45E S23 BT.
- A fir, 8 ins. diam., bears S 37° E 58 lks. (38.3 ft.) marked T6S R45E S26 BT.
- A fir, 10 ins. diam., bears S 53° W 50 lks. (33.0 ft.) marked T6S R45E S27 BT.
- A fir, 5 ins. diam., bears N 12° W 67 lks. (44.2 ft.) marked T6S R45E S22 BT.

**Lester E. Fischer, BLM 1974**

Found: The original granite stone, 12 x 12 x 6 ins. firmly set 3 ins. in the ground marked with 2 grooves on S and E faces from which the remains of the original bearing trees:

- A root hole, bears N 88° E 48 lks. (31.7 ft.) dist., with a down and decayed fir alongside, 5 ins. diam., with fragmentary scribe marks visible on an open decayed blaze.
- A white fir, 28 ins. diam., bears S 53° W 50 lks. (33.0 ft.) with a healed blaze.

Set: An iron post, 28 ins. long 2 1/2 ins. diam., 24 ins. in the ground, with brass cap from which new bearing trees:

- A subalpine fir, 9 ins. diam., bears N 67° E 42 lks. (27.7 ft.) marked T6S R45E S23 BT.
  - A western larch, 7 ins. diam., bears S 33 1/2° E 81 lks. (53.5 ft.) marked T6S R45E S26 BT.
  - A fir, 11 ins. diam., bears N 85° W 64 lks. (42.2 ft.) marked T6 S R45 E S22 BT.
- Bury corner stone alongside iron post.

**Philip Griffin, BLM, 1994**

Found: An iron post, 2 1/2 ins. diam., firmly set, projecting 6 ins. above the ground, with brass cap from which:

- A fir, 36 ins. diam., bears S 51 1/2° W 47 lks. (31.0 ft.) with a healed blaze. ((Record S 53° W 50 lks. (33.0 ft.)) (Original)
- A fir, 12 ins. diam., bears N 64 1/2° E 42 lks. (27.7 ft.) with fragmentary scribe marks on partially healed blaze. (Record N 67° E) (Fischer)
- A larch, 8 ins. diam., bears S 37° E 86 lks. (56.8 ft.) with a healed blaze. ((Record S 33 1/2° E 81 lks. (53.5 ft.)) (Fischer)
- A fir, 17 ins. diam., bears N 89° W 59 lks. (38.9 ft.) with a healed blaze. ((Record N 85° W 64 lks. (42.2 ft.)) (Fischer)

A steel fence post is alongside the iron post. The corner is located on a steep spur, sloping N.

119109

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Richard Chesebro*

**OREGON**  
JULY 18, 1980  
Richard A. Chesebro  
1886

Renews: 12-31-2009

Office of.....County...Surveyor..... County of.....Baker.....  
State of.....Oregon....., I hereby certify that the within was filed  
in this office for record on the..... day of....., 20.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan. 14, 2009  
BAKER COUNTY SURVEYOR  
SURVEY NO. 6-45-163