

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. P-1

History of original corner establishment:

Corner was originally established under GLO contract number 707, by Willard B. Blakeslee on August 15, 1901. Surveyor General's notes state: "Set a basalt stone 14 x 8 x 6 ins., 8 ins. in the grn., for 1/4 sec. cor. marked 1/4S on the W. face from which an alder 6 ins., in diam. brs. S85°E, 14 lks. dist. marked 1/4 S24 BT and a fir 8 ins. in diam. brs. N80°E, 10 lks. dist. marked T6S R48E 1/4 S19 BT."

DIAGRAM

T6S
R47E R48E
1/4
S24+S19

Description of corner evidence found:

Found no trace of original stone in mound of stone near a steel fence post. Corner falls on bank of creek and stone may have fallen in creek. Found a down 14" fir, clearly scribed T6S R47E BT. From center of root hole measured S80°W., 6.6 ft.

Description of monument and accessories established to perpetuate the original location of this corner:

At point measured from down BT, set 2 1/2" x 30" galvanized pipe and brass cap marked as shown.
Set pipe 22" in the ground and mound of stone around to cap.
From which by magnetic declination of N20°E:
A 10" fir, bears S77°W., 17.3 ft., scribed 1/4 S24 BT.
A 17" fir bears N18°E., 61.0 ft., scribed 1/4 S19 BT.
Painted blazes red and 6" red band around. Placed 54-3s, 4-4s and brass washers stamped PLS 1051 on the BTs.
Placed 54-4 on a steel fence post 5 ft. south of the corner.

T6S
R47E R48E
1/4
S24+S19
OR PLS 1051
1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1978
BARRY B. BARBOUR
1051

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David Cummins
Daniel Rowland
Brian Cays

April 29, 1981