

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by William R. Gradon under contract no. 445, dated June 1, 1882.

Surveyor's General record states:

Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S on N. face from which:

A pine 8 ins. diam. bears N. 65° W., 86 lks. dist. marked $\frac{1}{4}$ S BT
A pine 30 ins. diam. bears S. 75° E., 83 lks. dist. marked $\frac{1}{4}$ S BT

DIAGRAM

T 7 S R 38 E

$\frac{1}{4}$	S 21
	S 28

Description of corner evidence found:

Found a 12 inch extensively decayed pine stump marked $\frac{1}{4}$ S for section 21 BT

No trace of section 28 BT as it falls in the fill slope of a very old roadway.

Also, found a $\frac{1}{2}$ inch bolt, 11 inches long and a $\frac{1}{2}$ inch iron rod, 21 inches long and a wood lath alongside marked $\frac{1}{4}$ cor. common to secs. 21 & 28, T 7 S R 38 E WM, ORIS 645 at the record bearing and distance from the found original bearing tree.

Description of monument and accessories established to perpetuate the original location of this corner

Set a $2\frac{1}{2}$ inch brass cap on a 1 inch iron pipe, 24 inches long, 18 inches in the ground marked thus:

T 7 S R 38 E

$\frac{1}{4}$	S 21
	S 28

Cor. remonumented April 21, 1978

Witness: Art Keller

C S 1978

A recently scribed 30 inch pine bears S 82° W, 19.6 ft. dist. marked $\frac{1}{4}$ S BT (unrecorded)

Placed a Forest Service bearing tree tag (#54-3) on each of the original bearing tree stump and the 30 inch pine and a Forest Service warning sign (#54-4) on a fence post 10 ft. west of the corner monument.

Office of County Surveyor..... County of Baker
State of Oregon....., I hereby certify that the within instrument was filed in this office for record on the 21 st day of April, 1978

(COUNTY OFFICIAL)

by

(DEPUTY)

FILED April 21, 1978

BAKER COUNTY SURVEYOR

SURVEY NO. 7-38-10

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206