

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by William R. Gradon under G L O contract No. 445 dated June 1, 1882.

Surveyor's General records state:

Set a post 4 ft long, 4 ins square, 24 ins in the ground for cor to secs 20, 21, 28, and 29 marked: T 7 S S 21 on NE face, R 38 E S 28 on SE face, S 29 on Sw face, and S 20 on NW face with 2 notches on south edge and 4 notches on east edge from which:

A pine 30 ins diam bears N 40° E, 200 lks dist mkd T 7 S R 38 E S 21 BT
A pine 28 ins diam bears S 30° E, 97 lks dist mkd T 7 S R 38 E S 28 BT
A pine 15 ins diam bears S 60° W, 115 lks dist mkd T 7 S R 38 E S 29 BT
A pine 30 ins diam bears N 47° W, 50 lks dist mkd T 7 S R 38 E S 20 BT

Description of corner evidence found:

A 28 inch sawed stump with a portion of lower blaze(no visible scribes) for S 28 BT.
A 15 inch sawed stump with a portion of lower blaze(no visible scribes) for S 29 BT.
A 16 x 4 x 2 inch wood post with visible scribe marks(not legible) lying loose on the ground.
At corner location as determined by bearing tree stumps found rotten remains of post to a depth of 20 inches.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 2 inch iron pipe, 31 inches long 26 inches in the ground marked thus:

T 7 S R 38 E
S 20 S 21
S 29 S 28
1978
ORLS 1639

I hereby certify the above corner monument was re-established as herein described on October 28, 1978, witnessed by Brian Rutter.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of.....County Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 5..th day of.....December....., 1978
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO 799-509

FILED Dec. 5, 1978

BAKER COUNTY SURVEYOR

SURVEY NO. 7-38-13