

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established in 1881, by W.B.

Barr, under "General Land Office Contract"

No. 388, Surveyor General's Notes State:

Set stake 5 ft. long 5 in. diam. 24 in. in

ground for corner to T6S R37-38E

from which

Tamarack 12 in. diam bears S78E 16 lks dist.

" 22 in. diam bears S67W 30 " "

" 24 in. diam bears N67W 20 " "

" 8 in. diam bears N29E 53 " "

DIAGRAM

T6S R38E

S31

-.-

S6

C C

T7S R38E

1984

PLS 2065

Description of corner evidence found: original post, from 1' to 2' below ground level.

All traces of the original bearing trees have been lost to fencing and logging activity in the area.

Accepted remains of post as the original corner position and set

Closing Corner S 3 27'22"W along the line established between the

found post and the W 1/4 cor. of Sec. 6, a distance of 3.45 ft. to

an intersection with the Twp. line between T6&7S, as established

between the Standard Cor. bet. Sec. 36/31, T6S, R37&38E and the Corner to Secs. 31/32/5/6, T6&7S R38E.

Description of monument and accessories | established to perpetuate the

original location of this corner:

Set 2 1/2" aluminum pipe with 2-1/2" aluminum cap stamped as shown on the DIAGRAM, set 28" in the ground.

From which

A Pine 6" dia. bears N47E., 34.5 ft. scribed T6S R38E S31 CC BT

A Tamarack 8" dia. bears S81E., 19.4 ft. scribed T7S R38E S6 CC BT

Nailed a brass washer stamped PLS 2065, on blaze above BT scribe,

Bearing Tree Sign above blaze, and warning sign on back of each tree.

Painted a 6" red band at breast ht. around each tree.

Set steel post with warning and boundary signs, 3 ft. South from cor.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

Corner Set Sept. 10, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 2-15-85
BAKER COUNTY SURVEYOR
SURVEY NO. 7-38-29

☆ GPO-798-276