

History of original corner establishment:

Corner originally established in 1881, by Eugene P. McCornack, under "General Land Office Contract" No. 398, Surveyor Generals Notes State:

(Abridged notes) Set a post 24" in the ground, with standard markings. from which:

A Tamarack 8" dia. bears N50E 25 lks. mkd. 1/4 S BT

A Tamarack 10" dia. bears NBOW 13 lks. mkd. 1/4 S BT

In 1974 the Bureau of Land Management Remonumented this corner from existing physical evidence. See FIELD NOTES of the "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINT, TOWNSHIP 7 SOUTH, RANGE 38 EAST," as executed by Lester E. Fischer, Cadastral Surveyor and James J. Carlson, Cadastral Surveyor, under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey Group No. 350.

DIAGRAM

T7S
R37E1R38E
11/4S6
1
1975

Description of corner evidence found:

Found 3" brass cap monument on 2-1/2" pipe set 8" above the ground with cap stamped as shown on the DIAGRAM

Found a white fir, 7" dia. bears N78-1/2E, 32.3 ft. blaze open scribe reads X BT

Found white fir 8" dia. bears S46/1/4E, 16.5 ft. blaze open scribe reads 1/4 S6 BT

Both trees live in good condition.

Found remains of original bearing trees as described by the BLM

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained Corner by Setting steel posts with warning and boundary signs, North & South 5 ft. from cor.

Maintained accessories by painting the blaze and a 6" red band around the trees taken in 1975. Also nailed Bearing Tree signs to each tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

Corner Maintained Sept. 9, 1984
Witnessed by Douglas M. Ferguson PLS 848

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)