

History of original corner establishment:

Corner originally established in 1981, by William L. Hanley, PLS 1639, while subdividing Section 5, whereby he set a 5/8"x30" steel pin, with plastic cap, stamped HANLEY ENG. See Baker County Survey No. 7-38-20, as filed Nov. 18, 1981.

DIAGRAM

T7S R38E
W1/16
C--C
S5
R.M. 40.0→
1984
PLS 2065

Description of corner evidence found:

Found 5/8" steel pin with plastic cap stamped HANLEY ENG, set on the westerly edge of the Anthony Lakes Highway.

No accessories originally established.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

Description of monument and accessories I established to perpetuate the original location of this corner:

Accepted the said 5/8" pin with plastic cap as the 1/16 cor. Since it falls in the roadway the pin is not disturbed and is used to mark the true corner position.
From Which

Set 2-1/2" aluminum pipe with 2-1/2" aluminum cap stamped as shown on the DIAGRAM, set 26" in the ground for reference monument, bears S89° 57' 04"W, 40.0 ft. from the said pin.

A Pine 16" dia. bears N82° 52' W., 46.5 ft. from said pin, scribed C-W 1/16 S5 BT
A Pine 8" dia. bears S82° 56' W., 78.6 ft. from said pin, scribed C-W 1/16 S5 BT

Nailed a brass washer stamped PLS 848, on blaze above BT scribe, bearing tree sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree.
(Douglas M. Ferguson, PLS 848 scribed trees)

Set steel posts with warning and boundary signs, East & West 4 ft. from Reference Monument.

Corner Set Sept. 20, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)