

History of original corner establishment:
 Corner not previously established

DIAGRAM
 T7S R38E
 C1/4
 S5
 1984
 PLS 2065

Description of corner evidence found:
 Corner not previously established

Description of monument and accessories | established to perpetuate the
 original location of this corner:
 Set 2-1/2" aluminum pipe with 2-1/2" aluminum cap stamped as shown
 on the DIAGRAM, set 16" in the ground and raised a mound of stone &
 earth around the pipe.

From which

A Pine 20" dia. bears West, 12.7 ft. scribed C1/4 S5 BT
 A Pine 14" dia. bears N80E., 63.2 ft. scribed C1/4 S5 BT

Nailed a brass washer stamped PLS 848, on blaze above BT scribe,
 Bearing Tree Sign above blaze, and warning sign on back of each tree.
 Painted a 6" red band at breast ht. around each tree.
 (Douglas M. Ferguson, PLS 848 scribed trees)

Set steel posts with warning and boundary signs. North & West,
 3.5 ft. from cor.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

J. David Brinton

OREGON
 DECEMBER 2, 1983
 J. DAVID BRINTON
 2065

Corner set Sept. 20, 1984
 Witnessed by Douglas M. Ferguson.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)