

History of original corner establishment:

Corner originally established in 1882, by William R. Graddon, under "General Land Office Contract" No. 445, Surveyor General's Notes States: Set a basalt stone 22x12x6 in. 16 ins. in the ground for 1/4 sec. cor. mkd. 1/4 on W face. from which

DIAGRAM
T7S R38E
1/4
|
S5.S4
|
CS 1981

A pine 20 ins. diam. bears N60E., 22 lks dist. marked 1/4 S BT
A pine 18 in. diam. bears West, 12 lks. dist. marked 1/4 S BT
In 1957 James D Hanley PLS 1206 found the orig stone and bearing trees,
In 1981 William L. Hanley PLS 1639 found only the remains of the bearing trees and re monumented the corner at the same position as found by PLS 1206, in 1957. Set a 1" iron pipe with 2-1/2 " brass cap. stamped as shown on the DIAGRAM, set with 6" above the ground. (See CERTIFIED RECORD OF LAND CORNER MONUMENTATION, as filed July 9, 1981, in the office of the Baker Co. Surveyor.)

Description of corner evidence found:

Found 1" iron pipe with 2-1/2" brass cap stamped as shown on the DIAGRAM set with 6" above the ground.

Found remains of original bearing trees.

A pine stump no scribing visible bears record measurement to Section 4 BT

A stump hole bears approx. record measurement to Section 5 BT.

Found unrecorded bearing trees with Bearing Tree signs marked Hanley 1981.

A Fir. 7" dia. bears N56E., 40.4 ft. scribed 1/4 S4 BT

A Fir. 11" dia. bears N37-1/2W., 34.4 ft. scribed 1/4 S5 BT

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained Corner Monument by setting a steel post with warning sign, North 3 ft. from Corner.

Maintained Section 4 Bearing Tree by painting the solid wood on the stump and nailing bearing tree and warning signs. to the stump.

Maintained previously unrecorded bearing trees by painting a 6" red band around, nailing bearing tree signs above blaze and warning signs to back of those trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OFFICIAL
DEC. 17th 2, 1983
J. DAVID BRINTON
2065

Corner Maintained Sept. 19, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)