

History of original corner establishment:

Corner originally established in 1882, by William R. Grady, under "General Land Office Contract" No. 445, Surveyor General's Notes State: (Abridged Notes) Set post 4"x4", 24" in ground, with standard markings. From which:
 A tamarack 14" dia. bears N65E., 7 lks. (standard scribe)
 A pine 7" dia. bears S50E., 24 lks. (standard scribe)
 A fir 7" dia. bears S80W., 25 lks. " "
 A fir 6" dia. bears N40W., 11 lks. " "

DIAGRAM

BLM
 T7S R38E
 S61S5

 S71S8
 1974

In 1974 the Bureau of Land Management Re-monumented this corner. from existing physical evidence. See FIELD NOTES of the "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINT, TOWNSHIP 7 SOUTH, RANGE 38 EAST," as executed by Lester E. Fischer, Cadastral Surveyor and James J. Carlson, Cadastral Surveyor, under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey Group No. 350.

Description of corner evidence found:

Found 2-1/2 iron pipe with 3" brass cap stamped as shown on the DIAGRAM set with 6" above the ground.

Found original bearing trees as taken in 1882.

A root hole, bears N.65E., 7 lks. dist., with a down western larch stump alongside, 18 ins. diam., with scribe marks T7S R38E S5 BT.

A root hole, bears S.80W., 25 lks. dist., with a down fir stump alongside, 20 ins. diam., with healed double blaze.

Found trees as taken by the BLM, in 1974.

A ponderosa pine, 11 ins. diam. bears N.9E., 56 lks. dist. mkd. T7S R38E S5 BT

A fir, 8 ins. diam., bears S. 29E., 75 lks. dist., mkd. T7S R38E S8 BT

A western larch, 11ins. diam., bears S.28W., 32 lks. dist., mkd. T7S R38E S7 BT

A western larch, 7 ins. diam., bears N36-1/2W., 71 lks dist. mkd T7S R38E S6 BT

Section 5 Bearing tree is dead, all other trees are live in good condition.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained Corner Monument by setting a steel post with warning sign North 1 ft. from corner.

Maintained original bearing trees as taken in 1882.

Nailed Bearing Tree Sign above blaze, and warning sign on back of each tree.

Painted a 6" red band at breast ht. around each tree.

Scribed a new bearing tree.

A Fir, 13" dia. bears N23E., 27.7 ft. scribed T7S R38E S5 BT

Nailed a brass washer stamped PLS 848, on blaze above BT scribe,

Bearing Tree Sign above blaze, and warning sign on back of new tree.

Painted a 6" red band at breast ht. around new tree.

(Douglas M. Ferguson, PLS 848 scribed the new tree)

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

J David Brinton

OREGON
 DECEMBER 2, 1983
 J. DAVID BRINTON
 2065

Corner Maintained Sept. 19, 1984
 Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

..... by
 (COUNTY OFFICIAL)

(DEPUTY)