

History of original corner establishment:

Corner originally established in 1882, by William R. Graden, under "General Land Office Contract" No. 445, Surveyor General's Notes State: (Abridged Notes) Set post 4"x4", 24" in ground with standard markings, from which

- A pine 14" bears, N37E., 110 lks. (ad. scribe)
- A pine 20" bears, S25E., 70 lks. " "
- A pine 18" bears, S50W., 100 lks. " "
- A pine 14" bears, N60W., 50 lks. " "

In 1974 the Bureau of Land Management Remonumented this corner, from existing physical evidence. See FIELD NOTES of the "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINT, TOWNSHIP 7 SOUTH, RANGE 38 EAST," as executed by Lester E. Fischer, Cadastral Surveyor and James J. Carlson, Cadastral Surveyor, under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey Group No. 350.

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap monument stamped as shown on the DIAGRAM.

Found remains of original bearing trees.

A ponderosa pine snag, 24 ins. diam., bears S.25E., 70 lks. dist., with scribe T7S R38E S9 visible on opened blaze.

A splintered ponderosa pine snag, 20 ins. diam., bears S.50W., 100 lks. dist. with scribe T7S R38E S8 BT visible on open double blaze.

Found bearing trees taken by the BLM in 1974.

A ponderosa pine, 13 ins. diam., bears N.37E., 26 lks. mkd. T7S R38E S4 BT

A fir, 9 ins. diam., bears S.35E., 69 lks. mkd. T7S R38E S9 BT

A fir, 13 ins. diam., bears S.53W., 60 lks. mkd. T7S R38E S8 BT

A fir, 15 ins. diam., bears N.65W., 36 lks. mkd. T7S R38E S5 BT

Description of monument and accessories | established to perpetuate the original location of this corner:

Maintained Corner Monument by setting a post with warning sign North 2 ft. from corner.

Maintained original bearing trees by painting 6" red band around trees and painting detached scribe of S8 BT, nailing Bearing Tree sign to detached scribe of S8 BT, and nailing warning signs to back of trees. Maintained trees as taken by BLM in 1974 by painting a 6" red band around each tree, all these new trees are properly signed.

DIAGRAM

BLM
T7S R38E
S5|S4

S8|S9
1974

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

Corner Maintained Sept. 19, 1984
Witnessed by Douglas M. Ferguson, PLS B48

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)