

History of original corner establishment:

Corner originally established in 1881, by Eugene P. McCormack, under "General Land Office Contract" No. 398, Surveyor General's Notes State: (Unbridged Notes) Set post, 24" in ground with standard markings., from which: A Fir 20 ins. dia. bears N35E 40 lks. A Pine 8 ins dia. bears S50E 20 lks. A Fir 7 ins. dia. bears S55W 20 lks. A Fir 30 ins. dia. bears N55W 19 lks.

DIAGRAM
T7S1T7S
R37E1S7

1818
1R38E
1975

In 1974 the Bureau of Land Management Remonumented this corner. from existing physical evidence. See FIELD NOTES of the "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINT, TOWNSHIP 7 SOUTH, RANGE 38 EAST," as executed by Lester E. Fischer, Cadastral Surveyor and James J. Carlson, Cadastral Surveyor, under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey Group No. 350.

Description of corner evidence found:

Found 3" brass cap stamped as shown on the DIAGRAM, on 2-1/2" iron pipe set with 4" above the ground.

Found original bearing trees as follows:

A sawed fir stump, 25 ins. diam., bears N35E., 40 lks. dist., no marks.
A fir, 15 ins. diam., bears S47-3/4W., 20 lks. dist., with healed double blaze. (Record, S55W)
A fir snag, 26 ins. diam., bears N59-1/4W., 19 lks. dist., scribing reads R37, on partially healed blaze. (Record N55W) this tree is down.
Found trees taken in 1975 by BLN as follows:
A lodgepole pine, 6" dia. live in good condition, bears N19-1/4E., 25 lks. scribed T7S R38E S7 BT
A fir, 12" dia., live in good condition, bears S27E., 41 lks dist. scribed T7S R38E S18 BT

Description of monument and accessories | established to perpetuate the original location of this corner:

Maintained Corner by setting steel posts with warning and boundary signs North & South 5 ft. from Cor.

Maintained Accessories by Painting 6" red band around & nailing bearing tree or warning signs where needed at all bearing trees found and described above.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J David Brinton

ONCE
DECEMBER 11, 1983
J. DAVID BRINTON
2065

Corner maintained Sept. 11, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

★ GPO—798-276

FILED 2-15-85

BAKER COUNTY SURVEYOR
SURVEY NO. 7-38-45